

ESTIMATION DPR							
State	Odisha	District	Jagatsinghpur	Block	Tirtol	Gram Panchayat	Amberi

Work Code	OD/355/3393/118209/397499/00040230 (CONST. OF CC ROAD FROM KUNA SWAIN HOUSE TO GANDHARBA DAS HOUSE VILLAGE ERAGARI, AMBERI)
Project Category	Road

Financial Year	2023-24	Execution Level	PS
Executing Agency	Panchayat Samiti, Tirtol	Proposal Date	-
Date of Commencement	24-07-2025	Date of Completion	-
Scheme Name	5th SFC Grant in Aid	Scheme Component Name	MAINTENANCE OF ROADS AND BRIDGES
Project Sub-Category	CC Road	Project Type	New Work
Name of Executant	LIPSA SAMAL		

Administrative Approval Details

Approval No.	OD/355/3393/118209/397499/00040230/AS
--------------	---------------------------------------

Technical Sanction Details

Technical Sanction No.	OD/355/3393/118209/397499/00040230/TS
Fund Sanction No.	
Fund Sanction Amount (in Rs.)	100000

LABOUR STATEMENT

Sl.No.	Activity Name	Qty/unit(B=Analysis Basic Qty/HeaderUnit)	Quantity(Measurement Qty)	Unit
1	Earth Work (AR0115) : Filling foundation and plinth with sand well watered and rammed - Filling foundation and plinth with sand well watered and rammed including cost, conveyance, royalty, taxes of all materials, labours and T & P required for the work etc. complete and as per direction of Engineer-in charge.	-	5.2	Cum
i	Un-Skilled	0.1236	0.64272	-

2	Concrete (AR0303) : Cement concrete (1:3:6) with 4 cm. Crusher Broken hard granite metal - Cement concrete (1:3:6) with 4 cm. hard granite(Crusher Broken) metal including laying in layers not exceeding 300 mm in depth, ramming, compacting to proper thickness, watering and curing for proper period with cost conveyance, royalty, taxes of all materials, labour and T&P required for the work etc. complete and as per direction of Engineer-in charge.	-	6	Cum
i	Skilled	0.18	1.08	-
ii	Un-Skilled	3.9	23.4	-
3	Concrete (AR0307) : Cement concrete (1:2:4)with 12mm size hard broken granite chips per 1cum - Cement concrete work with (1:2:4) using 12mm size hard granite(crusher broken) chips including hoisting and laying in position compacting to specified design section and curing for proper period with cost conveyance, royalty, taxes of all materials, labour and T&P required for the work etc. complete as per specificaion and direction of Engineer-in charge.	-	6	Cum
i	Un-Skilled	4.6	27.6	-
ii	Skilled	0.68	4.08	-

4	R.C.C. Work (AR0410c) : R.C.C. foundation , plinth band and footings bases of columns mass concrete precast slabs etc - Rigid and smooth centring and shuttering for R.C.C. works including false works and dismantling them after casting including cost of materials complete in ground floor R.C.C. foundation, plinth band and footings bases of columns mass concrete precast slabs, etc	-	8	Sqm
i	Semi-Skilled	0.05	0.4	-
ii	Skilled	0.05	0.4	-

Sl.No.	Labour Type	Qty Unit	Rate	Amount
0	Un-Skilled	51.64272	462	23858.93664
1	Skilled	5.56	562	3124.72
2	Semi-Skilled	0.4	512	204.8
				Total: 27188.45664