

ESTIMATION DPR							
State	Odisha	District	Ganjam	Block	Patrapur	Gram Panchayat	Kharinipada

Work Code	OD/354/3379/117886/413145/00017479 (IMPROVEMENT OF ROAD WITH CC /PAVER BLOCK WITH CD WORKS FROM KHARANIPADA VILLAGE TO GOPINATHPUR BIDYAPITHA)
Project Category	Road

Financial Year	2021-22	Execution Level	PS
Executing Agency	Panchayat Samiti, Patrapur	Proposal Date	25-11-2021
Date of Commencement	08-06-2025	Date of Completion	-
Scheme Name	5th SFC Grant in Aid	Scheme Component Name	Maintenance and improvement of Road infrastructure
Project Sub-Category	Pavor Block	Project Type	Upgradation or Improvement
Name of Executant	RAJALAXMI SINGH		

Administrative Approval Details

Approval No.	OD/354/3379/117886/413145/00017479/AS
--------------	---------------------------------------

Technical Sanction Details

Technical Sanction No.	OD/354/3379/117886/413145/00017479/TS
Fund Sanction No.	12614
Fund Sanction Amount (in Rs.)	600000

LABOUR STATEMENT

Sl.No.	Activity Name	Qty/unit(B=Analysis Basic Qty/HeaderUnit)	Quantity(Measurement Qty)	Unit
--------	---------------	---	---------------------------	------

1	Earth Work (AR0102aa) : Earth work in hard soil or gravelly soil foundation & plinth within 50m. Initial lead and 1.5m initial lift - Earth work in hard soil or gravelly soil foundation & plinth within 50m. Initial lead and 1.5m initial lift including rough dressing and breaking clods to maximum 5cm to 7cm and laying in layers not exceeding 0.3m in depth and as per the direction of the Engineer-in-charge	-	11.47741875	Cum
i	Un-Skilled	0.516	5.922348075	-
2	Earth Work (AR0115) : Filling foundation and plinth with sand well watered and rammed - Filling foundation and plinth with sand well watered and rammed including cost, conveyance, royalty, taxes of all materials, labours and T & P required for the work etc. complete and as per direction of Engineer-in charge.	-	37.999542	Cum
i	Un-Skilled	0.1236	4.6967433912	-

3	Concrete (AR0303) : Cement concrete (1:3:6) with 4 cm. Crusher Broken hard granite metal - Cement concrete (1:3:6) with 4 cm. hard granite(Crusher Broken) metal including laying in layers not exceeding 300 mm in depth, ramming, compacting to proper thickness, watering and curing for proper period with cost conveyance, royalty, taxes of all materials, labour and T&P required for the work etc. complete and as per direction of Engineer-in charge.	-	51.92547675	Cum
i	Skilled	0.18	9.346585815	-
ii	Un-Skilled	3.9	202.509359325	-
4	Concrete (AR0307) : Cement concrete (1:2:4)with 12mm size hard broken granite chips per 1cum - Cement concrete work with (1:2:4) using 12mm size hard granite(crusher broken) chips including hoisting and laying in position compacting to specified design section and curing for proper period with cost conveyance, royalty, taxes of all materials, labour and T&P required for the work etc. complete as per specificaion and direction of Engineer-in charge.	-	39.2238	Cum
i	Un-Skilled	4.6	180.42948	-
ii	Skilled	0.68	26.672184	-

5	R.C.C. Work (AR0410c) : R.C.C. foundation , plinth band and footings bases of columns mass concrete precast slabs etc - Rigid and smooth centring and shuttering for R.C.C. works including false works and dismantling them after casting including cost of materials complete in ground floor R.C.C. foundation, plinth band and footings bases of columns mass concrete precast slabs, etc	-	111.950074	Sqm
i	Semi-Skilled	0.05	5.5975037	-
ii	Skilled	0.05	5.5975037	-

Sl.No.	Labour Type	Qty Unit	Rate	Amount
0	Un-Skilled	393.5579307912	462	181823.76402553
1	Skilled	41.616273515	562	23388.34571543
2	Semi-Skilled	5.5975037	512	2865.9218944
Total: 208078.03163536				