

Estimate Abstract

OD/367/3527/120677/406281/00013786 : MAINT OF NATUGAON MAHADEV POKHARI

Block : Nayagarh, Panchayat : Natugaon

Created By:Krushna Chandra Acharya

Sl No	Description of work	Quantity	Unit	Rate in (Rs.)	Amount (Rs.)
1	Earth Work : AR0102aa (Earth work in hard soil or gravelly soil foundation & plinth within 50m. Initial lead and 1.5m initial lift) : Earth work in hard soil or gravelly soil foundation & plinth within 50m. Initial lead and 1.5m initial lift including rough dressing and breaking clods to maximum 5cm to 7cm and laying in layers not exceeding 0.3m in depth and as per the direction of the Engineer-in-charge	11.5	Cubic Meter	235.56432	2708.98968

2	<p>Earth Work : AR0115 (Filling foundation and plinth with sand well watered and rammed) : Filling foundation and plinth with sand well watered and rammed including cost, conveyance, royalty, taxes of all materials, labours and T & P required for the work etc. complete and as per direction of Engineer-in charge.</p>	1.5	Cubic Meter	779.535372	1169.303058
3	<p>Concrete : AR0303a (Cement concrete (1:3:6) with 4 cm. hard granite(Hand Broken) metal) : Cement concrete (1:3:6) with 4 cm. hard granite(Hand Broken) metal including laying in layers not exceeding 300 mm in depth, ramming, compacting to proper thickness, watering and curing for proper period with cost conveyance, royalty, taxes of all materials, labour and T&P required for the work etc. complete and as per direction of Engineer-in charge.</p>	16.14999961853	Cubic Meter	5130.2318043	82853.241682417

4	<p>Concrete : AR0307 (Cement concrete (1:2:4)with 12mm size hard broken granite chips per 1cum) : Cement concrete work with (1:2:4) using 12mm size hard granite(crusher broken) chips including hoisting and laying in position compacting to specified design section and curing for proper period with cost conveyance, royalty, taxes of all materials, labour and T&P required for the work etc. complete and as per direction of Engineer-in charge.</p>	0.25	Cubic Meter	6905.5061581	1726.376539525
5	<p>R.C.C. Work : AR0410c (R.C.C. foundation , plinth band and footings bases of columns mass concrete precast slabs etc) : Rigid and smooth centering and shuttering for R.C.C. works including false works and dismantling them after casting including cost of materials complete in ground floor R.C.C. foundation, plinth band and footings bases of columns mass concrete precast slabs, etc</p>	42	Square Meter	215.22489289764	9039.4455017009

6	Plastering : AR1027 (6mm thick cement Plaster in CM (1:4) over R.C.C. surfaces including chipping (Inside)) : 6mm thick cement Plaster in CM (1:4) over R.C.C. surfaces in inside including chipping with proper level and line, curing for the proper period with cost conveyance, royalty, taxes of all materials, labor, and T & P required for the work, etc comp. and as per the direction of the Engineer-in-charge.	11.5	Square Meter	188.731628384	2170.413726416
---	---	------	-----------------	---------------	----------------

Total Amount:	99667.770188059
----------------------	-----------------

Display Citizen Board (+) @	332.25
Any Other Lumpsum (+) @	0

Total Amount:	100000.02018806
----------------------	-----------------

Grand Net Total Amount	99999.9985
-------------------------------	------------

Krushna Chandra Acharya
JE
Nayagarh Block

Chandra Sekhar Samantaray
AEE
Nayagarh Block

Padma Charan Sahoo
BDO
Nayagarh Block