

**Estimate Abstract**

**OD/357/3404/118523/381146/00016322 : Improvement of Road from Padmalochan Pradhan  
house to Bada Kata, Katikela  
Block : Jharsuguda, Gram Panchayat : Katikela  
Created By:Rasmita maharana**

Sl No	Description of work	Quantity	Unit	Rate in (Rs.)	Amount (Rs.)
1	<b>Earth Work : AR0102a (Earth work in hard soil or gravelly soil within 50m. Initial lead and 1.5m initial lift) :</b> Earth work in hard soil or gravelly soil within 50m. Initial lead and 1.5m initial lift including rough dressing and breaking clods to maximum 5cm to 7cm and laying in layers not exceeding 0.3m in depth and as per the direction of the Engineer-in-charge	59.76	Cubic Meter	200.6466	11990.640816
2	<b>Earth Work : AR0115 (Filling foundation and plinth with sand well watered and rammed) :</b> Filling foundation and plinth with sand well watered and rammed including cost, conveyance, royalty, taxes of all materials, labours and T & P required for the work etc. complete and as per direction of Engineer-in charge.	29.88	Cubic Meter	974.966332	29131.99400016

3	<p><b>Concrete : AR0303 (Cement concrete (1:3:6) with 4 cm. Crusher Broken hard granite metal) :</b> Cement concrete (1:3:6) with 4 cm. hard granite(Crusher Broken) metal including laying in layers not exceeding 300 mm in depth, ramming, compacting to proper thickness, watering and curing for proper period with cost conveyance, royalty, taxes of all materials, labour and T&amp;P required for the work etc. complete and as per direction of Engineer-in charge.</p>	29.88	Cubic Meter	5990.620878	178999.75183464
4	<p><b>R.C.C. Work : AR0410c (R.C.C. foundation , plinth band and footings bases of columns mass concrete precast slabs etc) :</b> Rigid and smooth centring and shuttering for R.C.C. works including false works and dismantling them after casting including cost of materials complete in ground floor R.C.C. foundation, plinth band and footings bases of columns mass concrete precast slabs, etc</p>	33.2	Square Meter	216.23489289764	7178.9984442016

5	<b>Concrete : AR0307 (Cement concrete (1:2:4)with 12mm size hard broken granite chips per 1cum) : Cement concrete work with (1:2:4) using 12mm size hard granite(crusher broken) chips including hoisting and laying in position compacting to specified design section and curing for proper period with cost conveyance, royalty, taxes of all materials, labour and T&amp;P required for the work etc. complete as per specificaion and direction of Engineer-in charge.</b>	22.41	Cubic Meter	7492.771153	167913.00153873
---	---	-------	----------------	-------------	-----------------

<b>Total Amount:</b>	395214.38663373
----------------------	-----------------

Provision for Contingency (+) @	3952.1438663373
Display Citizen Board (+) @	833
Any Other Lumpsum (+) @	

<b>Total Amount:</b>	399999.53050007
----------------------	-----------------

<b>Grand Net Total Amount</b>	399999.53050007
-------------------------------	-----------------

**Rasmita maharana  
JE  
Jharsuguda Block**

**PRIYANKA SAHOO  
AEE  
Jharsuguda Block**

**Anil Kumar Acharya  
BDO  
Jharsuguda Block**