

Estimate Abstract

OD/354/3378/117862/412577/00017507 : CONSTRUCTION O CC CUM PAVER ROAD FROM KUMBHARA SAHI TO ANANTA NAGAR DAKHINAPUR
Block : Kukudakhandi, Gram Panchayat : Dakhinapur
Created By:ASWIN SUBUDHI

Sl No	Quantity	Unit	Rate in (Rs.)	Amount (Rs.)
1	Earth Work : AR0102aa (Earth work in hard soil or gravelly soil foundation & plinth within 50m. Initial lead and 1.5m initial lift) : Earth work in hard soil or gravelly soil foundation & plinth within 50m. Initial lead and 1.5m initial lift including rough dressing and breaking clods to maximum 5cm to 7cm and laying in layers not exceeding 0.3m in depth and as per the direction of the Engineer-in-charge			
	7.2	Cubic Meter	240.77592	1733.586624
2	Earth Work : AR0115 (Filling foundation and plinth with sand well watered and rammed) : Filling foundation and plinth with sand well watered and rammed including cost, conveyance, royalty, taxes of all materials, labours and T & P required for the work etc. complete and as per direction of Engineer-in charge.			
	20.4	Cubic Meter	804.488432	16411.5640128
3	Concrete : AR0307 (Cement concrete (1:2:4)with 12mm size hard broken granite chips per 1cum) : Cement concrete work with (1:2:4) using 12mm size hard granite(crusher broken) chips including hoisting and laying in position compacting to specified design section and curing for proper period with cost conveyance, royalty, taxes of all materials, labour and T&P required for the work etc. complete as per specifaion and direction of Engineer-in charge.			
	6.44	Cubic Meter	7143.7167286	46005.535732184
4	miscellaneous : ARM287 (Supplying and fixing of 80mm thick cement concrete interlocking paver block of M-40 grade of approved make, design, colour and size made by Block making machine with proper compaction laid in required pattern etc. complete in all respect conforming to IRC) : Supplying and fixing of 80mm thick cement concrete interlocking paver block of M-40 grade of approved make, design, colour and size made by Block making machine with proper compaction laid in required pattern etc. complete in all respect conforming to IRC SP-63:2018. (New miscellaneous items) and as directed by Engineer-in-Charge.			
	180	Square Meter	630.5826	113504.868
5	Road Work : AR1311i (Spreading metal for patch or pothole repairs and consolidation with H.R.R. with crusher dust) : Supplying and spreading metal for patch or pothole repairs and consolidation with H.R.R. or rammers with crusher dust and sand blinding, etc. complete including cost, conveyance, royalty, taxes cost of all labour & material, hire charges of T & P materials required for work as per specification and direction of Engineer-in-Charge.			
	4.673625	Cubic Meter	2589.4557915604	12102.145323831
6	R.C.C. Work : AR0410c (R.C.C. foundation , plinth band and footings bases of columns mass concrete precast slabs etc) : Rigid and smooth centring and shuttering for R.C.C. works including false works and dismantling them after casting including cost of materials complete in ground floor R.C.C. foundation, plinth band and footings bases of columns mass concrete precast slabs, etc			
	32	Square Meter	216.23489289764	6919.5165727245

Total Amount:	196677.21626554
----------------------	-----------------

Provision for Contingency (+) @	2000
Display Citizen Board (+) @	1322
Any Other Lumpsum (+) @	0
Provision for survey investigation and quality control (+) @	

Total Amount:	199999.21626554
----------------------	-----------------

Grand Net Total Amount	199999.21626554
-------------------------------	-----------------

ASWIN SUBUDHI
JE
Kukudakhandi Block

ANURAG RATH
AEE
Kukudakhandi Block

PALLAVI SWAIN
BDO
Kukudakhandi Block