

**Estimate Abstract**

**OD/354/3378/117858/412605/00017506 : CONSTRUCTION OF CC CUM PAVER ROAD FROM MAJHI SAHI  
KOTHAGHARA LADU CHHAKA AT BORIGAM  
Block : Kukudakhandi, Gram Panchayat : Barigam  
Created By:G SANKAR ACHARY**

Sl No	Quantity	Unit	Rate in (Rs.)	Amount (Rs.)
1	<b>Earth Work : AR0102aa (Earth work in hard soil or gravelly soil foundation &amp; plinth within 50m. Initial lead and 1.5m initial lift) :</b> Earth work in hard soil or gravelly soil foundation & plinth within 50m. Initial lead and 1.5m initial lift including rough dressing and breaking clods to maximum 5cm to 7cm and laying in layers not exceeding 0.3m in depth and as per the direction of the Engineer-in-charge			
	6.2775	Cubic Meter	240.77592	1511.4708378
2	<b>Earth Work : AR0115 (Filling foundation and plinth with sand well watered and rammed) :</b> Filling foundation and plinth with sand well watered and rammed including cost, conveyance, royalty, taxes of all materials, labours and T & P required for the work etc. complete and as per direction of Engineer-in charge.			
	44.5625	Cubic Meter	804.488432	35850.015751
3	<b>Concrete : AR0307 (Cement concrete (1:2:4)with 12mm size hard broken granite chips per 1cum) :</b> Cement concrete work with (1:2:4) using 12mm size hard granite(crusher broken) chips including hoisting and laying in position compacting to specified design section and curing for proper period with cost conveyance, royalty, taxes of all materials, labour and T&P required for the work etc. complete as per specifaion and direction of Engineer-in charge.			
	2.79	Cubic Meter	7143.7167286	19930.969672794
4	<b>miscellaneous : ARM287 (Supplying and fixing of 80mm thick cement concrete interlocking paver block of M-40 grade of approved make, design, colour and size made by Block making machine with proper compaction laid in required pattern etc. complete in all respect conforming to IRC) :</b> Supplying and fixing of 80mm thick cement concrete interlocking paver block of M-40 grade of approved make, design, colour and size made by Block making machine with proper compaction laid in required pattern etc. complete in all respect conforming to IRC SP-63:2018. (New miscellaneous items) and as directed by Engineer-in-Charge.			
	207.7	Square Meter	630.5826	130972.00602
5	<b>R.C.C. Work : AR0410c (R.C.C. foundation , plinth band and footings bases of columns mass concrete precast slabs etc) :</b> Rigid and smooth centring and shuttering for R.C.C. works including false works and dismantling them after casting including cost of materials complete in ground floor R.C.C. foundation, plinth band and footings bases of columns mass concrete precast slabs, etc			
	37.2	Square Meter	216.23489289764	8043.9380157922
<b>Total Amount:</b>				196308.40029739
Provision for Contingency (+) @				1963.0840029739

Display Citizen Board (+) @	1000
Any Other Lumpsum (+) @	728
Provision for survey investigation and quality control (+) @	

<b>Total Amount:</b>	199999.48430036
----------------------	-----------------

<b>Grand Net Total Amount</b>	199999.48430036
-------------------------------	-----------------

**G SANKAR ACHARY**  
**JE**  
**Kukudakhandi Block**

**ANURAG RATH**  
**AEE**  
**Kukudakhandi Block**

**PALLAVI SWAIN**  
**BDO**  
**Kukudakhandi Block**