

Estimate Abstract

**OD/354/3369/117686/412103/00014069 : Construction of CC/Paver road from nua sahi Raghunath temple to Reddy Street Humar
Block : Chatrapur, Gram Panchayat : Podapadar
Created By:RASMITA KUMARI SAHU**

Sl No	Quantity	Unit	Rate in (Rs.)	Amount (Rs.)
1	Earth Work : AR0102aa (Earth work in hard soil or gravelly soil foundation & plinth within 50m. Initial lead and 1.5m initial lift) : Earth work in hard soil or gravelly soil foundation & plinth within 50m. Initial lead and 1.5m initial lift including rough dressing and breaking clods to maximum 5cm to 7cm and laying in layers not exceeding 0.3m in depth and as per the direction of the Engineer-in-charge			
	4.9695984	Cubic Meter	240.77592	1196.5596267905
2	R.C.C. Work : AR0410c (R.C.C. foundation , plinth band and footings bases of columns mass concrete precast slabs etc) : Rigid and smooth centring and shuttering for R.C.C. works including false works and dismantling them after casting including cost of materials complete in ground floor R.C.C. foundation, plinth band and footings bases of columns mass concrete precast slabs, etc			
	38.26117152	Square Meter	216.23489289764	8273.4003257654
3	Concrete : AR0307 (Cement concrete (1:2:4)with 12mm size hard broken granite chips per 1cum) : Cement concrete work with (1:2:4) using 12mm size hard granite(crusher broken) chips including hoisting and laying in position compacting to specified design section and curing for proper period with cost conveyance, royalty, taxes of all materials, labour and T&P required for the work etc. complete as per specifaion and direction of Engineer-in charge.			
	7.686312192	Cubic Meter	7509.75866822	57722.349610517
4	miscellaneous : ARM287 (Supplying and fixing of 80mm thick cement concrete interlocking paver block of M-40 grade of approved make, design, colour and size made by Block making machine with proper compaction laid in required pattern etc. complete in all respect conforming to IRC) : Supplying and fixing of 80mm thick cement concrete interlocking paver block of M-40 grade of approved make, design, colour and size made by Block making machine with proper compaction laid in required pattern etc. complete in all respect conforming to IRC SP-63:2018. (New miscellaneous items) and as directed by Engineer-in-Charge.			
	152.175114	Square Meter	651.5586	99151.00423268
5	Earth Work : AR0115a (Filling foundation and plinth with crusher dust well watered and rammed) : Filling foundation and plinth with crusher dust well watered and rammed including cost, conveyance, royalty, taxes of all materials, labours and T & P required for the work etc. complete and as per direction of Engineer-in charge.			
	16.962895872	Cubic Meter	727.152732	12334.616075956

Total Amount:	178677.92987171
----------------------	-----------------

Provision for Contingency (+) @	1786.7792987171
---------------------------------	-----------------

Display Citizen Board (+) @	1845
Any Other Lumpsum (+) @	17690
Provision for survey investigation and quality control (+) @	

Total Amount:	199999.70917043
----------------------	-----------------

Grand Net Total Amount	199999.70917043
-------------------------------	-----------------

RASMITA KUMARI SAHU
JE
Chatrapur Block

LAGNAJEET SAHOO
AEE
Chatrapur Block

Sri Sambit Sangramjeet Sahoo
BDO
Chatrapur Block