

Estimate Abstract

**OD/346/3309/116318/393756/00063203 : Maintenance of Khajuridiha Kalika Thakurani Pokhari (Pucca Ghat Guard Wall)
Block : Soro, Gram Panchayat : Madhusuidanpur
Created By:Monalisa Pati**

Sl No	Quantity	Unit	Rate in (Rs.)	Amount (Rs.)
1	Earth Work : AR0102aa (Earth work in hard soil or gravelly soil foundation & plinth within 50m. Initial lead and 1.5m initial lift) : Earth work in hard soil or gravelly soil foundation & plinth within 50m. Initial lead and 1.5m initial lift including rough dressing and breaking clods to maximum 5cm to 7cm and laying in layers not exceeding 0.3m in depth and as per the direction of the Engineer-in-charge			
	8.7408	Cubic Meter	240.77592	2104.574161536
2	Earth Work : AR0115 (Filling foundation and plinth with sand well watered and rammed) : Filling foundation and plinth with sand well watered and rammed including cost, conveyance, royalty, taxes of all materials, labours and T & P required for the work etc. complete and as per direction of Engineer-in charge.			
	2.0496	Cubic Meter	1493.995232	3062.0926275072
3	Concrete : AR0303 (Cement concrete (1:3:6) with 4 cm. Crusher Broken hard granite metal) : Cement concrete (1:3:6) with 4 cm. hard granite(Crusher Broken) metal including laying in layers not exceeding 300 mm in depth, ramming, compacting to proper thickness, watering and curing for proper period with cost conveyance, royalty, taxes of all materials, labour and T&P required for the work etc. complete and as per direction of Engineer-in charge.			
	10.7904	Cubic Meter	6052.17287774	65305.366219966
4	Plastering : AR1004 (12mm thick cement plaster (1:6) over Brick work in inside) : 12mm thick cement plaster (1:6) over Brick work in inside including racking out joints finishing smooth with proper plumb and line curing for proper period with cost conveyance, royalty, taxes of all materials, labour and T & P required for the work etc. comp.and as per direction of Engineer-in-charge.			
	16.8	Square Meter	180.2285061348	3027.8389030646
5	R.C.C. Work : AR0410c (R.C.C. foundation , plinth band and footings bases of columns mass concrete precast slabs etc) : Rigid and smooth centring and shuttering for R.C.C. works including false works and dismantling them after casting including cost of materials complete in ground floor R.C.C. foundation, plinth band and footings bases of columns mass concrete precast slabs, etc			
	19.668	Square Meter	216.29483748359	4254.0868636272
6	Concrete : AR0307 (Cement concrete (1:2:4)with 12mm size hard broken granite chips per 1cum) : Cement concrete work with (1:2:4) using 12mm size hard granite(crusher broken) chips including hoisting and laying in position compacting to specified design section and curing for proper period with cost conveyance, royalty, taxes of all materials, labour and T&P required for the work etc. complete as per specifaion and direction of Engineer-in charge.			
	6.2496	Cubic Meter	7469.65532138	46682.357896496

7	Masonry Brick Work : AR0603bi (Flyash Bricks of size (25cm x 12cm x 8cm) in cement mortar (1:6) in superstructure) : Brickwork with Flyash Bricks of size (25cm x 12cm x 8cm) in cement mortar (1:6) in superstructure having crushing strength not less than 75.00 Kg/cm ² with dimensional tolerance ±8 percent immersing the bricks in water not less than six hours with cost conveyance, royalty, taxes of all materials, labor, and T&P required for the work, etc. complete and as per direction of Engineer-in-charge.			
	2.1	Cubic Meter	5500.606513832	11551.273679047
8	Special items for irrigation works : AR0201 (Excavation of any approved type of soil in an approved borrow area by mechanical means loading into and transportation by mechanical means and unloading the soil within an initial lead of 1km) : Excavation of any approved type of soil in an approved borrow area by mechanical means loading into and transportation by mechanical means and unloading the soil within an initial lead of 1km on a properly prepared and scientifically approved surface including spreading and leveling the earth in 22.5 cm layers to make ready for watering and compaction with sheep foot rollers and dozers but excluding watering and compaction in dams and dykes for all heights including construction, maintenance, watering and lighting of haul road and borrow area, etc. complete as per the direction of Engineer-in charge. (measurement of the fill to be taken on the finished compacted section under OMC condition).			
	6049.92	Cubic Meter	56.56	342183.4752

Total Amount:	478171.06555124
----------------------	-----------------

Display Citizen Board (+) @	5000
Any Other Lumpsum (+) @	5000
Provision for survey investigation and quality control (+) @	6828.93
Provision for Contingency (+) @	5000

Total Amount:	499999.99555124
----------------------	-----------------

Grand Net Total Amount	499999.99555124
-------------------------------	-----------------

Monalisa Pati
JE
Soro Block

Nirmala Kanta Parida
AEE
Soro Block

Satyanath Naik
BDO
Soro Block