

Estimate Abstract

**OD/362/3465/119685/408003/00063059 : maintenance of road from pmgsy road to dhani routaray chhak
Block : Tangi, Gram Panchayat : Badapokharia
Created By:PRIYADARSHINI MOHAPATRA**

Sl No	Quantity	Unit	Rate in (Rs.)	Amount (Rs.)
1	Earth Work : AR0102aa (Earth work in hard soil or gravelly soil foundation & plinth within 50m. Initial lead and 1.5m initial lift) : Earth work in hard soil or gravelly soil foundation & plinth within 50m. Initial lead and 1.5m initial lift including rough dressing and breaking clods to maximum 5cm to 7cm and laying in layers not exceeding 0.3m in depth and as per the direction of the Engineer-in-charge			
	2.9520264	Cubic Meter	240.77592	710.77687232429
2	Earth Work : AR0115 (Filling foundation and plinth with sand well watered and rammed) : Filling foundation and plinth with sand well watered and rammed including cost, conveyance, royalty, taxes of all materials, labours and T & P required for the work etc. complete and as per direction of Engineer-in charge.			
	14.681411296	Cubic Meter	1293.257732	18986.848675224
3	Concrete : AR0303 (Cement concrete (1:3:6) with 4 cm. Crusher Broken hard granite metal) : Cement concrete (1:3:6) with 4 cm. hard granite(Crusher Broken) metal including laying in layers not exceeding 300 mm in depth, ramming, compacting to proper thickness, watering and curing for proper period with cost conveyance, royalty, taxes of all materials, labour and T&P required for the work etc. complete and as per direction of Engineer-in charge.			
	18.066401568	Cubic Meter	5628.5695615	101687.99795148
4	R.C.C. Work : AR0410c (R.C.C. foundation , plinth band and footings bases of columns mass concrete precast slabs etc) : Rigid and smooth centring and shuttering for R.C.C. works including false works and dismantling them after casting including cost of materials complete in ground floor R.C.C. foundation, plinth band and footings bases of columns mass concrete precast slabs, etc			
	51.654068	Square Meter	216.23489289764	11169.411861707
5	Concrete : AR0307 (Cement concrete (1:2:4)with 12mm size hard broken granite chips per 1cum) : Cement concrete work with (1:2:4) using 12mm size hard granite(crusher broken) chips including hoisting and laying in position compacting to specified design section and curing for proper period with cost conveyance, royalty, taxes of all materials, labour and T&P required for the work etc. complete as per specifaion and direction of Engineer-in charge.			
	16.059023616	Cubic Meter	7080.5862645	113707.30203673

Total Amount:	246262.33739747
----------------------	-----------------

Provision for Contingency (+) @	2500
Display Citizen Board (+) @	1237.55

Any Other Lumpsum (+) @	
Provision for survey investigation and quality control (+) @	
Total Amount:	249999.88739747
Grand Net Total Amount	249999.88739747

PRIYADARSHINI MOHAPATRA
JE
Tangi Block

ASHOK KUMAR NANDA
AEE
Tangi Block

Rumana Jafri
BDO
Tangi Block