

**Estimate Abstract**

**OD/346/3309/116318/393756/00062685 : Completion of Aproch road with perfrial Development of Khajuridiha Tahkurani  
Block : Soro, Gram Panchayat : Madhusuidanpur  
Created By:Monalisa Pati**

Sl No	Quantity	Unit	Rate in (Rs.)	Amount (Rs.)
1	<b>Earth Work : AR0102aa (Earth work in hard soil or gravelly soil foundation &amp; plinth within 50m. Initial lead and 1.5m initial lift) :</b> Earth work in hard soil or gravelly soil foundation & plinth within 50m. Initial lead and 1.5m initial lift including rough dressing and breaking clods to maximum 5cm to 7cm and laying in layers not exceeding 0.3m in depth and as per the direction of the Engineer-in-charge			
	1.57725	Cubic Meter	240.77592	379.76381982
2	<b>Earth Work : AR0115 (Filling foundation and plinth with sand well watered and rammed) :</b> Filling foundation and plinth with sand well watered and rammed including cost, conveyance, royalty, taxes of all materials, labours and T & P required for the work etc. complete and as per direction of Engineer-in charge.			
	10.71315	Cubic Meter	1493.995232	16005.395019701
3	<b>Concrete : AR0303 (Cement concrete (1:3:6) with 4 cm. Crusher Broken hard granite metal) :</b> Cement concrete (1:3:6) with 4 cm. hard granite(Crusher Broken) metal including laying in layers not exceeding 300 mm in depth, ramming, compacting to proper thickness, watering and curing for proper period with cost conveyance, royalty, taxes of all materials, labour and T&P required for the work etc. complete and as per direction of Engineer-in charge.			
	10.71315	Cubic Meter	5491.78286174	58834.29356525
4	<b>miscellaneous : ARM287 (Supplying and fixing of 80mm thick cement concrete interlocking paver block of M-40 grade of approved make, design, colour and size made by Block making machine with proper compaction laid in required pattern etc. complete in all respect conforming to IRC) :</b> Supplying and fixing of 80mm thick cement concrete interlocking paver block of M-40 grade of approved make, design, colour and size made by Block making machine with proper compaction laid in required pattern etc. complete in all respect conforming to IRC SP-63:2018. (New miscellaneous items) and as directed by Engineer-in-Charge.			
	109.039	Square Meter	651.063	70991.258457
5	<b>Other Building Items. : AR1911 (Stainless steel of 304 grade in hand railing using 50mm dia of 2mm) :</b> Supplying, fitting and fixing of Stainless steel of 304 grade in hand railing using 50mm dia of 2mm thick circular pipe with Balustrade of size 32mm x 32mm x 2mm @ 0.90mtr. C/C and stainless square pipe bracing of size 32mm x 32mm x 2mm in 3 rows in staircase as per approved design and specification, buffing, polishing etc with cost,conveyance, taxes of all materials, labour,T&P etc. required for the complete in all respect. and as per direction of Engineer in Charge			
	15.218663513003	Meter	3129.0244276074	47619.569887724
<b>Total Amount:</b>			193830.28074949	

Provision for Contingency (+) @	2000
Display Citizen Board (+) @	500
Any Other Lumpsum (+) @	2000
Provision for survey investigation and quality control (+) @	3707.71

<b>Total Amount:</b>	202037.99074949
----------------------	-----------------

<b>Grand Net Total Amount</b>	202037.99074949
-------------------------------	-----------------

**Monalisa Pati**  
**JE**  
**Soro Block**

**Nirmala Kanta Parida**  
**AEE**  
**Soro Block**

**Satyanath Naik**  
**BDO**  
**Soro Block**