

Estimate Abstract

**OD/360/3440/119191/396265/00063967 : CONSTRUCTION OF CC ROAD FROM SUNAKAR BEHERA HOUSE TO LAXMAN SAHOO HOUSE, GP NARASINGHPUR
Block : Pattamundai, Gram Panchayat : Narasinghpur
Created By:BINAY KUMAR MISHRA**

Sl No	Quantity	Unit	Rate in (Rs.)	Amount (Rs.)
1	Earth Work : AR0102aa (Earth work in hard soil or gravelly soil foundation & plinth within 50m. Initial lead and 1.5m initial lift) : Earth work in hard soil or gravelly soil foundation & plinth within 50m. Initial lead and 1.5m initial lift including rough dressing and breaking clods to maximum 5cm to 7cm and laying in layers not exceeding 0.3m in depth and as per the direction of the Engineer-in-charge			
	2.6	Cubic Meter	240.77592	626.017392
2	Earth Work : AR0115 (Filling foundation and plinth with sand well watered and rammed) : Filling foundation and plinth with sand well watered and rammed including cost, conveyance, royalty, taxes of all materials, labours and T & P required for the work etc. complete and as per direction of Engineer-in charge.			
	18.2	Cubic Meter	1014.477532	18463.4910824
3	Concrete : AR0303 (Cement concrete (1:3:6) with 4 cm. Crusher Broken hard granite metal) : Cement concrete (1:3:6) with 4 cm. hard granite(Crusher Broken) metal including laying in layers not exceeding 300 mm in depth, ramming, compacting to proper thickness, watering and curing for proper period with cost conveyance, royalty, taxes of all materials, labour and T&P required for the work etc. complete and as per direction of Engineer-in charge.			
	20.02	Cubic Meter	6270.60340018	125537.4800716
4	R.C.C. Work : AR0410c (R.C.C. foundation , plinth band and footings bases of columns mass concrete precast slabs etc) : Rigid and smooth centring and shuttering for R.C.C. works including false works and dismantling them after casting including cost of materials complete in ground floor R.C.C. foundation, plinth band and footings bases of columns mass concrete precast slabs, etc			
	31.2	Square Meter	216.23489289764	6746.5286584064
5	miscellaneous : ARM287 (Supplying and fixing of 80mm thick cement concrete interlocking paver block of M-40 grade of approved make, design, colour and size made by Block making machine with proper compaction laid in required pattern etc. complete in all respect conforming to IRC) : Supplying and fixing of 80mm thick cement concrete interlocking paver block of M-40 grade of approved make, design, colour and size made by Block making machine with proper compaction laid in required pattern etc. complete in all respect conforming to IRC SP-63:2018. (New miscellaneous items) and as directed by Engineer-in-Charge.			
	156	Square Meter	629.0079	98125.2324

Total Amount:	249498.74960441
----------------------	-----------------

Provision for Contingency (+) @	2500
---------------------------------	------

Display Citizen Board (+) @	950
Any Other Lumpsum (+) @	
Provision for survey investigation and quality control (+) @	

Total Amount:	252948.74960441
----------------------	-----------------

Grand Net Total Amount	252948.74960441
-------------------------------	-----------------

BINAY KUMAR MISHRA
JE
Pattamundai Block

Rosalin Mahalik
AEE
Pattamundai Block

SHEETAL AGRAWAL
BDO
Pattamundai Block