

Estimate Abstract

**OD/366/3520/120549/427209/00064028 : Const. of CC road from PMGSY road to Hiralal House
Block : Raighar, Gram Panchayat : Naktisimoda
Created By:TANMAY PATRNAIK**

Sl No	Quantity	Unit	Rate in (Rs.)	Amount (Rs.)
1	Earth Work : AR0102aa (Earth work in hard soil or gravelly soil foundation & plinth within 50m. Initial lead and 1.5m initial lift) : Earth work in hard soil or gravelly soil foundation & plinth within 50m. Initial lead and 1.5m initial lift including rough dressing and breaking clods to maximum 5cm to 7cm and laying in layers not exceeding 0.3m in depth and as per the direction of the Engineer-in-charge			
	16.575	Cubic Meter	240.77592	3990.860874
2	Earth Work : AR0115 (Filling foundation and plinth with sand well watered and rammed) : Filling foundation and plinth with sand well watered and rammed including cost, conveyance, royalty, taxes of all materials, labours and T & P required for the work etc. complete and as per direction of Engineer-in charge.			
	14.025	Cubic Meter	854.362232	11982.4303038
3	R.C.C. Work : AR0410c (R.C.C. foundation , plinth band and footings bases of columns mass concrete precast slabs etc) : Rigid and smooth centring and shuttering for R.C.C. works including false works and dismantling them after casting including cost of materials complete in ground floor R.C.C. foundation, plinth band and footings bases of columns mass concrete precast slabs, etc			
	23.375	Square Meter	216.39264180804	5058.1780022629
4	Concrete : AR0303a (Cement concrete (1:3:6) with 4 cm. hard granite(Hand Broken) metal) : Cement concrete (1:3:6) with 4 cm. hard granite(Hand Broken) metal including laying in layers not exceeding 300 mm in depth, ramming, compacting to proper thickness, watering and curing for proper period with cost conveyance, royalty, taxes of all materials, labour and T&P required for the work etc. complete and as per direction of Engineer-in charge.			
	17.425	Cubic Meter	5198.86718048	90590.260619864
5	Concrete : AR0307 (Cement concrete (1:2:4)with 12mm size hard broken granite chips per 1cum) : Cement concrete work with (1:2:4) using 12mm size hard granite(crusher broken) chips including hoisting and laying in position compacting to specified design section and curing for proper period with cost conveyance, royalty, taxes of all materials, labour and T&P required for the work etc. complete as per specifaion and direction of Engineer-in charge.			
	11.15625	Cubic Meter	7439.58028676	82997.817574166

Total Amount:	194619.54737409
----------------------	-----------------

Provision for Contingency (+) @	2000
Display Citizen Board (+) @	2697

Any Other Lumpsum (+) @	683
Provision for survey investigation and quality control (+) @	
Total Amount:	199999.54737409
Grand Net Total Amount	199999.54737409

TANMAY PATTNAIK
JE
Raighar Block

SIDDHARTH SHANKAR RANA
AEE
Raighar Block

RITU SINGH
BDO
Raighar Block