

**Estimate Abstract**

**OD/355/3386/118044/398353/00064282 : Repair and maintenance of AWC building at Ambasala-A  
Block : Balikuda, Gram Panchayat : Ambasala  
Created By:SANJAY KUMAR KALLO**

SI No	Quantity	Unit	Rate in (Rs.)	Amount (Rs.)
1	<b>Painting : AR0918gk (Finishing wall with two coats weather coat paint of approved shade including one coat of oil bound primer in the outer surface of old work(Outside)(For repair and maintenance) .) :</b> Finishing wall with two coats weather coat paint of approved shade including one coat of oil bound primer in the outer surface of old work to give an even shade including all costs of labour, Paint, Brushes, and putty required for the work, etc. complete and as per direction of Engineer-in-charge(Outside)(For repair and maintenance).			
	104.382	Square Meter	159.28472551378	16626.458218579
2	<b>Other Building Items. : AR1901B (Vitrified Tile 600mmx600mm Plain Ivory) :</b> Supplying, fitting & fixing Vitrified Tile 600mmx600mm Plain Ivory in floors of size 600mm x 600 mm of approved make conforming IS:13755 laid on 20 mm thick cement mortar(1:4)and filling joints with white cement of approved quality including cost of all materials, taxes, labour, T&P , etc. required for the work all complete as per direction of Engineer-in-charge(for new work only)			
	27.815	Square Meter	1011.4768163238	28134.227646046

<b>Total Amount:</b>	44760.685864626
----------------------	-----------------

Provision for PH Work (+) @	
Provision for EI Work (+) @	
Provision for Contingency (+) @	39
Display Citizen Board (+) @	200
Any Other Lumpsum (+) @	
Provision for survey investigation and quality control (+) @	

<b>Total Amount:</b>	44999.685864626
----------------------	-----------------

<b>Grand Net Total Amount</b>	44999.685864626
-------------------------------	-----------------

**SANJAY KUMAR KALLO**  
**JE**  
**Balikuda Block**

**DIPTI REKHA MALLICK**  
**AEE**  
**Balikuda Block**

**Sagar Kumar Nanda**  
**BDO**  
**Balikuda Block**