

**Estimate Abstract**

**OD/358/3418/118789/422969/00063543 : CONSTRUCTION OF CC ROAD FROM RD ROAD TO CHANCHARA PADA**

**Block : Lanjigarh, Gram Panchayat : BATERIMA  
Created By:SMITA BISWAL**

Sl No	Quantity	Unit	Rate in (Rs.)	Amount (Rs.)
1	<b>Earth Work : AR0102aa (Earth work in hard soil or gravelly soil foundation &amp; plinth within 50m. Initial lead and 1.5m initial lift) :</b> Earth work in hard soil or gravelly soil foundation & plinth within 50m. Initial lead and 1.5m initial lift including rough dressing and breaking clods to maximum 5cm to 7cm and laying in layers not exceeding 0.3m in depth and as per the direction of the Engineer-in-charge			
	3.928	Cubic Meter	240.77592	945.76781376
2	<b>Earth Work : AR0115 (Filling foundation and plinth with sand well watered and rammed) :</b> Filling foundation and plinth with sand well watered and rammed including cost, conveyance, royalty, taxes of all materials, labours and T & P required for the work etc. complete and as per direction of Engineer-in charge.			
	16.9395	Cubic Meter	583.278232	9880.441610964
3	<b>Concrete : AR0303 (Cement concrete (1:3:6) with 4 cm. Crusher Broken hard granite metal) :</b> Cement concrete (1:3:6) with 4 cm. hard granite(Crusher Broken) metal including laying in layers not exceeding 300 mm in depth, ramming, compacting to proper thickness, watering and curing for proper period with cost conveyance, royalty, taxes of all materials, labour and T&P required for the work etc. complete and as per direction of Engineer-in charge.			
	22.8315	Cubic Meter	5736.95259686	130983.23321521
4	<b>Concrete : AR0307 (Cement concrete (1:2:4)with 12mm size hard broken granite chips per 1cum) :</b> Cement concrete work with (1:2:4) using 12mm size hard granite(crusher broken) chips including hoisting and laying in position compacting to specified design section and curing for proper period with cost conveyance, royalty, taxes of all materials, labour and T&P required for the work etc. complete as per specification and direction of Engineer-in charge.			
	13.441125	Cubic Meter	7268.51497682	97697.01836781
5	<b>R.C.C. Work : AR0410c (R.C.C. foundation , plinth band and footings bases of columns mass concrete precast slabs etc) :</b> Rigid and smooth centring and shuttering for R.C.C. works including false works and dismantling them after casting including cost of materials complete in ground floor R.C.C. foundation, plinth band and footings bases of columns mass concrete precast slabs, etc			
	36.825	Square Meter	216.23489289764	7962.8499309556
<b>Total Amount:</b>				247469.3109387
Provision for Contingency (+) @				2530

Display Citizen Board (+) @	2988
Any Other Lumpsum (+) @	
Provision for survey investigation and quality control (+) @	

<b>Total Amount:</b>	252987.3109387
----------------------	----------------

<b>Grand Net Total Amount</b>	252987.3109387
-------------------------------	----------------

**SMITA BISWAL**  
**JE**  
**Lanjigarh Block**

**SANTOSH KUMAR BEHERA**  
**AEE**  
**Lanjigarh Block**

**Animesh Pradhan IAS**  
**BDO**  
**Lanjigarh Block**