

Estimate Abstract

**OD/370/3553/121193/426232/00063638 : Improvement of road from SC Sahi to Masani
Block : Kolnara, Gram Panchayat : Badakhilapadar
Created By: Babulu Hembram**

Sl No	Quantity	Unit	Rate in (Rs.)	Amount (Rs.)
1	Earth Work : AR0102aa (Earth work in hard soil or gravelly soil foundation & plinth within 50m. Initial lead and 1.5m initial lift) : Earth work in hard soil or gravelly soil foundation & plinth within 50m. Initial lead and 1.5m initial lift including rough dressing and breaking clods to maximum 5cm to 7cm and laying in layers not exceeding 0.3m in depth and as per the direction of the Engineer-in-charge			
	13.3	Cubic Meter	240.77592	3202.319736
2	Earth Work : AR0115 (Filling foundation and plinth with sand well watered and rammed) : Filling foundation and plinth with sand well watered and rammed including cost, conveyance, royalty, taxes of all materials, labours and T & P required for the work etc. complete and as per direction of Engineer-in charge.			
	9.8	Cubic Meter	825.880232	8093.6262736
3	Concrete : AR0303 (Cement concrete (1:3:6) with 4 cm. Crusher Broken hard granite metal) : Cement concrete (1:3:6) with 4 cm. hard granite(Crusher Broken) metal including laying in layers not exceeding 300 mm in depth, ramming, compacting to proper thickness, watering and curing for proper period with cost conveyance, royalty, taxes of all materials, labour and T&P required for the work etc. complete and as per direction of Engineer-in charge.			
	13.3	Cubic Meter	5373.97343174	71473.846642142
4	Concrete : AR0307 (Cement concrete (1:2:4)with 12mm size hard broken granite chips per 1cum) : Cement concrete work with (1:2:4) using 12mm size hard granite(crusher broken) chips including hoisting and laying in position compacting to specified design section and curing for proper period with cost conveyance, royalty, taxes of all materials, labour and T&P required for the work etc. complete as per specification and direction of Engineer-in charge.			
	6.86	Cubic Meter	6877.01034938	47176.290996747
5	R.C.C. Work : AR0410b (centering and shuttering fRigid and smooth or R.C.C. works including false works and dismantling them after casting) : Rigid and smooth centring and shuttering for R.C.C. works including false works and dismantling them after casting including cost of materials complete in ground floor R.C.C. stairs excluding landing but including railing details for 5 Sqm			
	9.52	Square Meter	918.337198106	8742.5701259691

Total Amount:	138688.65377446
----------------------	-----------------

Provision for Contingency (+) @	1386.8865377446
Display Citizen Board (+) @	3700

Any Other Lumpsum (+) @	
Provision for survey investigation and quality control (+) @	

Total Amount:	143775.5403122
----------------------	----------------

Grand Net Total Amount	143775.5403122
-------------------------------	----------------

Babulu Hembram
JE
Kolnara Block

SAMEER KUMAR RATHA
AEE
Kolnara Block

SMT REENA PRADHAN
BDO
Kolnara Block