

Estimate Abstract

**OD/362/3462/119640/408122/00064090 : Construction of Paver Road from village road to Arada UP School.
Block : Chilika, Gram Panchayat : Chndeswar
Created By:AMITA PRUSTY**

Sl No	Quantity	Unit	Rate in (Rs.)	Amount (Rs.)
1	Earth Work : AR0115 (Filling foundation and plinth with sand well watered and rammed) : Filling foundation and plinth with sand well watered and rammed including cost, conveyance, royalty, taxes of all materials, labours and T & P required for the work etc. complete and as per direction of Engineer-in charge.			
	22.908149616	Cubic Meter	1214.477732	27821.437589956
2	miscellaneous : ARM287 (Supplying and fixing of 80mm thick cement concrete interlocking paver block of M-40 grade of approved make, design, colour and size made by Block making machine with proper compaction laid in required pattern etc. complete in all respect conforming to IRC) : Supplying and fixing of 80mm thick cement concrete interlocking paver block of M-40 grade of approved make, design, colour and size made by Block making machine with proper compaction laid in required pattern etc. complete in all respect conforming to IRC SP-63:2018. (New miscellaneous items) and as directed by Engineer-in-Charge.			
	150.31612497	Square Meter	642.7605	96617.26764378
3	Concrete : AR0307 (Cement concrete (1:2:4)with 12mm size hard broken granite chips per 1cum) : Cement concrete work with (1:2:4) using 12mm size hard granite(crusher broken) chips including hoisting and laying in position compacting to specified design section and curing for proper period with cost conveyance, royalty, taxes of all materials, labour and T&P required for the work etc. complete as per specifaion and direction of Engineer-in charge.			
	1.5645032	Cubic Meter	7417.4630886	11604.644737997
4	Masonry Brick Work : AR0603b (Flyash Bricks of size (25cm x 12cm x 8cm) in cement mortar (1:6) in foundation and plinth) : Brickwork with Flyash Bricks of size (25cm x 12cm x 8cm) in cement mortar (1:6) in foundation and plinth having crushing strength not less than 75.00 Kg/cm2 with dimensional tolerance ±8 percent immersing the bricks in water not less than six hours with cost conveyance, royalty, taxes of all materials, labor, and T&P required for the work, etc. complete and as per direction of Engineer-in-charge.			
	1.2121431275168	Cubic Meter	5306.22145004	6431.8998637482

Total Amount:	142475.24983548
----------------------	-----------------

Provision for Contingency (+) @	780
Display Citizen Board (+) @	500
Any Other Lumpsum (+) @	
Provision for survey investigation and quality control (+) @	

Total Amount:	143755.24983548
----------------------	-----------------

Grand Net Total Amount	143755.24983548
-------------------------------	-----------------

AMITA PRUSTY
JE
Chilika Block

MADHUSMITA TRPATHY
AEE
Chilika Block

Poonam Mahapatra
BDO
Chilika Block