

Estimate Abstract

**OD/361/3453/119492/385689/00063996 : Construction of culvert at Ninhan Munda sahi
Block : Patana, Gram Panchayat : Turumunga
Created By:Phillip Kumar Mohanta**

Sl No	Quantity	Unit	Rate in (Rs.)	Amount (Rs.)
1	Earth Work : AR0102aa (Earth work in hard soil or gravelly soil foundation & plinth within 50m. Initial lead and 1.5m initial lift) : Earth work in hard soil or gravelly soil foundation & plinth within 50m. Initial lead and 1.5m initial lift including rough dressing and breaking clods to maximum 5cm to 7cm and laying in layers not exceeding 0.3m in depth and as per the direction of the Engineer-in-charge			
	20.95615	Cubic Meter	240.77592	5045.736295908
2	Earth Work : AR0115 (Filling foundation and plinth with sand well watered and rammed) : Filling foundation and plinth with sand well watered and rammed including cost, conveyance, royalty, taxes of all materials, labours and T & P required for the work etc. complete and as per direction of Engineer-in charge.			
	32.7933325	Cubic Meter	705.750832	23143.921695928
3	Concrete : AR0303 (Cement concrete (1:3:6) with 4 cm. Crusher Broken hard granite metal) : Cement concrete (1:3:6) with 4 cm. hard granite(Crusher Broken) metal including laying in layers not exceeding 300 mm in depth, ramming, compacting to proper thickness, watering and curing for proper period with cost conveyance, royalty, taxes of all materials, labour and T&P required for the work etc. complete and as per direction of Engineer-in charge.			
	46.34245275	Cubic Meter	5985.18866774	277368.32303458
4	R.C.C. Work : AR0404A (Reinforced cement concrete work of M-20 grade with 20mm & down grade size black hard crusher broken granite chips) : Reinforced cement concrete work of M-20 grade with 20mm & down grade size black hard crusher broken granite chips including hoisting and laying in position compacting to specified design section and curing for proper period with cost conveyance, royalty,taxes of all materials, labour and T&P required for the work etc. complete and as per direction of Engineer-in charge. (excluding centring and shuttering)			
	0.6792	Cubic Meter	6194.7991207398	4207.5075628065
5	R.C.C. Work : AR0410c (R.C.C. foundation , plinth band and footings bases of columns mass concrete precast slabs etc) : Rigid and smooth centring and shuttering for R.C.C. works including false works and dismantling them after casting including cost of materials complete in ground floor R.C.C. foundation, plinth band and footings bases of columns mass concrete precast slabs, etc			
	85.638007	Square Meter	216.23489289764	18517.925271612
6	R.C.C. Work : AR0404Ag (Reinforced cement concrete work of M-20 grade with 20mm & down grade size black hard crusher broken granite chips) : Reinforced cement concrete work of M-20 grade with 20mm & down grade size black hard crusher broken granite chips including hoisting and laying in position compacting to specified design section and curing for proper period with cost conveyance, royalty,taxes of all materials, labour and T&P required for the work etc. (including centring and shuttering) complete and as per direction of Engineer-in charge (RCC Roof slab, landing, balcony, sun shade)			
	2.7168	Cubic Meter	12821.035864476	34832.190236608

7	R.C.C. Work : AR0409 (Supplying, fitting, and placing uncoated HYSD bar reinforcement including labor charges for cutting, bending, binding, and tying the grills and placing in position) : Supplying, fitting, and placing uncoated HYSD bar reinforcement including labor charges for cutting, bending, binding, and tying the grills and placing in position including cost of binding wire 18 to 20 gauge with cost of steel rod and as per drawing, design, and direction of Engineer-in-charge.			
	3.4	Quintal	9273.5808522	31530.17489748
8	Concrete : AR0307 (Cement concrete (1:2:4)with 12mm size hard broken granite chips per 1cum) : Cement concrete work with (1:2:4) using 12mm size hard granite(crusher broken) chips including hoisting and laying in position compacting to specified design section and curing for proper period with cost conveyance, royalty, taxes of all materials, labour and T&P required for the work etc. complete as per specificaion and direction of Engineer-in charge.			
	11.6495535	Cubic Meter	7468.05426938	86999.497752046
9	Plastering : AR1017 (20mm thick cement Plaster in CM (1:4) over brick work in inside.) : 20mm thick cement Plaster in CM (1:4) over stone work in inside including racking out joints finishing smooth with proper plumb and line, curing for proper period with cost conveyance, royalty, taxes of all materials, labour and T & P required for the work etc comp.and as per direction of Engineer-in-charge.			
	23.36435	Square Meter	270.6011802464	6322.42068569

Total Amount:	487967.69743265
----------------------	-----------------

Provision for PH Work (+) @	
Provision for EI Work (+) @	
Provision for Contingency (+) @	5000
Display Citizen Board (+) @	5000
Any Other Lumpsum (+) @	2032
Provision for survey investigation and quality control (+) @	

Total Amount:	499999.69743265
----------------------	-----------------

Grand Net Total Amount	499999.69743265
-------------------------------	-----------------

Phillip Kumar Mohanta
JE
Patana Block

SUSMITA BEHERA
AEE
Patana Block

KendujharPatanaBDO
BDO
Patana Block