

Estimate Abstract

**OD/354/3382/275072/412714/00064838 : CONSTRUCTION OF PAVER ROAD AT GOPAL GAON VILLAGE ROAD
Block : Rangeilunda, Gram Panchayat : Chandapur
Created By:CHANDRA SEKHAR SARANGI**

| Sl No | Quantity | Unit | Rate in (Rs.) | Amount (Rs.) |
|-------|--|--------------|---------------|-----------------|
| 1 | Concrete : AR0307 (Cement concrete (1:2:4)with 12mm size hard broken granite chips per 1cum) : Cement concrete work with (1:2:4) using 12mm size hard granite(crusher broken) chips including hoisting and laying in position compacting to specified design section and curing for proper period with cost conveyance, royalty, taxes of all materials, labour and T&P required for the work etc. complete as per specifaion and direction of Engineer-in charge. | | | |
| | 9.2644 | Cubic Meter | 7336.09831882 | 67964.549264876 |
| 2 | miscellaneous : ARM287 (Supplying and fixing of 80mm thick cement concrete interlocking paver block of M-40 grade of approved make, design, colour and size made by Block making machine with proper compaction laid in required pattern etc. complete in all respect conforming to IRC) : Supplying and fixing of 80mm thick cement concrete interlocking paver block of M-40 grade of approved make, design, colour and size made by Block making machine with proper compaction laid in required pattern etc. complete in all respect conforming to IRC SP-63:2018. (New miscellaneous items) and as directed by Engineer-in-Charge. | | | |
| | 294.072 | Square Meter | 651.1716 | 191491.3347552 |
| 3 | Earth Work : AR0102a (Earth work in hard soil or gravelly soil within 50m. Initial lead and 1.5m initial lift) : Earth work in hard soil or gravelly soil within 50m. Initial lead and 1.5m initial lift including rough dressing and breaking clods to maximum 5cm to 7cm and laying in layers not exceeding 0.3m in depth and as per the direction of the Engineer-in-charge | | | |
| | 7.9396 | Cubic Meter | 200.6466 | 1593.05374536 |
| 4 | Earth Work : AR0115a (Filling foundation and plinth with crusher dust well watered and rammed) : Filling foundation and plinth with crusher dust well watered and rammed including cost, conveyance, royalty, taxes of all materials, labours and T & P required for the work etc. complete and as per direction of Engineer-in charge. | | | |
| | 29.4972 | Cubic Meter | 725.132732 | 21389.38522235 |

| | |
|----------------------|-----------------|
| Total Amount: | 282438.32298779 |
|----------------------|-----------------|

| | |
|--|-------|
| Provision for Contingency (+) @ | 0 |
| Display Citizen Board (+) @ | 700 |
| Any Other Lumpsum (+) @ | 16861 |
| Provision for survey investigation and quality control (+) @ | 0 |

| | |
|----------------------|-----------------|
| Total Amount: | 299999.32298779 |
|----------------------|-----------------|

| | |
|-------------------------------|-----------------|
| Grand Net Total Amount | 299999.32298779 |
|-------------------------------|-----------------|

CHANDRA SEKHAR SARANGI
JE
Rangeilunda Block

DIGAMBAR NAYAK
AEE
Rangeilunda Block

BISWAJIT RAY
BDO
Rangeilunda Block