

Estimate Abstract

**OD/354/3367/117633/410591/00064407 : Completion of Incomplete AWC Building at Dandipadar
Block : Bhanjanagar, Gram Panchayat : Badakodanda
Created By:MADHU BEHERA**

SI No	Quantity	Unit	Rate in (Rs.)	Amount (Rs.)
1	Flooring : AR0817aa (Fixing Vitrified tiles of premium grade having thickness 8mm to 10mm confirming to IS 13756 of size 600mmx600mm plain (Ivory) in dados skirting and risers of steps on 12mm thick cement plaster (1:3)) : Fixing Vitrified tiles of premium grade having thickness 8mm to 10mm confirming to IS 13756 of size 600mmx600mm plain (Ivory) in dados skirting and risers of steps on 12mm thick cement plaster (1:3) jointed with neat cement slurry mixed with pigments to match the shade of the Vitrified tiles including rubbing and polishing complete including cost of precast tiles.			
	3.1965	Square Meter	1529.894790776	4890.3086987155
2	Flooring : AR0816 (Fixing ceramic Tiles (30cmx30cm / 40cmx40cm special plain/printed series ceramic floor tiles of premium grade having thickness 7mm to 8mm confirming to IS 13755) in floor) : Fixing ceramic Tiles (30cmx30cm / 40cmx40cm special plain/printed series ceramic floor tiles of premium grade having thickness 7mm to 8mm confirming to IS 13755) in floor , treads or steps and landing on a 25mm thick bed of cement mortar 1:1 (1cement: 1sand) jointed with neat cement slurry mixed with pigment to match the shades of the ceramic tiles including rubbing and polishing, cost of precast tiles complete as per direction of Engineer-in-charge.			
	7.467	Square Meter	1195.2597435668	8925.0045052133
3	Flooring : AR0817b (Fixing ceramic tiles (20cmx30cm / 20cmx20cm special plain/printed series ceramic wall tiles of premium grade having thickness 6.5mm to 6.7mm confirming to IS 13753)) : Fixing ceramic tiles (20cmx30cm / 20cmx20cm special plain/printed series ceramic wall tiles of premium grade having thickness 6.5mm to 6.7mm confirming to IS 13753) in wall cladding on 12mm thick cement plaster (1:3) jointed with neat cement slurry mixed with pigments to match the shade of the ceramic tiles including rubbing and polishing, cost of precast tiles complete as per direction of Engineer-in-charge.			
	23.8978	Square Meter	879.959790776	21029.103088007
4	Other Building Items. : AR1901B (Vitrified Tile 600mmx600mm Plain Ivory) : Supplying, fitting & fixing Vitrified Tile 600mmx600mm Plain Ivory in floors of size 600mm x 600 mm of approved make conforming IS:13755 laid on 20 mm thick cement mortar(1:4)and filling joints with white cement of approved quality including cost of all materials, taxes, labour, T&P , etc. required for the work all complete as per direction of Engineer-in-charge(for new work only)			
	44.5889	Square Meter	1008.2360980846	44956.138553884
5	Painting : AR0903i (Painting two coats of enamel paint in outer surface paint (outer surface)) : Painting two coats of enamel paint in outer surface paint including all costs of labour, Paint and brushes required for the work etc. complete and as per direction of Engineer-in-charge.(Outside)			
	50.136525	Square Meter	164.23523221452	8234.1838258041

6	Painting : AR0901d (Priming one coat with inner surface primer of approved quality water-bound primer over plastering surfaces (Inner surface)) : Priming one coat with inner surface primer of approved quality water-bound primer over plastering surfaces including cost conveyance, taxes of all materials, labor and T&P required for the work complete as per direction of the Engineer-in-charge.			
	190.293	Square Meter	71.83753306751	13670.179680016
7	Painting : AR0920 (Finishing wall two coats with plastic emulsion paint of approved shades on new work (Inside)) : Finishing wall two coats with plastic emulsion paint of approved shades on new work to give an even shade including all costs of labor, Paint and Brushes required for the work, etc. complete and as per direction of the Engineer-in-charge.(Inside)			
	242.3489	Square Meter	94.76013415	22965.014275105
8	Painting : AR0901di (Priming one coat with outer surface primer of approved quality water-bound primer over plastering surfaces(outer surface)) : Priming one coat with outer surface primer of approved quality water-bound primer over plastering surfaces including cost conveyance, taxes of all materials, labor and T&P required for the work complete as per direction of the Engineer-in-charge.			
	102.978	Square Meter	72.855030353548	7502.4653157477
9	Painting : AR0918ca (Finishing wall two coats with weather coat with one coat oilbound Primer) : Finishing wall surface two coats with weather coat with one coat oilbound Primer including all costs of labour, Paint, Primer, Brushes and putty required for the work etc. complete and as per direction of Engineer-in-charge.(Outside)			
	102.978	Square Meter	156.86604451751	16153.751532324

Total Amount:	148326.14947482
----------------------	-----------------

Provision for PH Work (+) @	26000
Provision for EI Work (+) @	22500
Provision for Contingency (+) @	2000
Display Citizen Board (+) @	1000
Any Other Lumpsum (+) @	173
Provision for survey investigation and quality control (+) @	

Total Amount:	199999.14947482
----------------------	-----------------

Grand Net Total Amount	199999.14947482
-------------------------------	-----------------

MADHU BEHERA
JE
Bhanjanagar Block

NITYANANDA PATRO
AEE
Bhanjanagar Block

BHARATEE DEVI
BDO
Bhanjanagar Block