

Estimate Abstract

**OD/354/3367/117652/410593/00064411 : Construction of CC/Paver road from Harijana Sahi to Gudi Sahi,
Binjhagiri
Block : Bhanjanagar, Gram Panchayat : Sanakodanda
Created By:MADHU BEHERA**

Sl No	Quantity	Unit	Rate in (Rs.)	Amount (Rs.)
1	Earth Work : AR0102aa (Earth work in hard soil or gravelly soil foundation & plinth within 50m. Initial lead and 1.5m initial lift) : Earth work in hard soil or gravelly soil foundation & plinth within 50m. Initial lead and 1.5m initial lift including rough dressing and breaking clods to maximum 5cm to 7cm and laying in layers not exceeding 0.3m in depth and as per the direction of the Engineer-in-charge			
	4.8438	Cubic Meter	240.77592	1166.270401296
2	Earth Work : AR0115 (Filling foundation and plinth with sand well watered and rammed) : Filling foundation and plinth with sand well watered and rammed including cost, conveyance, royalty, taxes of all materials, labours and T & P required for the work etc. complete and as per direction of Engineer-in charge.			
	21.63915	Cubic Meter	683.086432	14781.409765013
3	Concrete : AR0303 (Cement concrete (1:3:6) with 4 cm. Crusher Broken hard granite metal) : Cement concrete (1:3:6) with 4 cm. hard granite(Crusher Broken) metal including laying in layers not exceeding 300 mm in depth, ramming, compacting to proper thickness, watering and curing for proper period with cost conveyance, royalty, taxes of all materials, labour and T&P required for the work etc. complete and as per direction of Engineer-in charge.			
	4.238325	Cubic Meter	5385.31614786	22824.720062379
4	R.C.C. Work : AR0410c (R.C.C. foundation , plinth band and footings bases of columns mass concrete precast slabs etc) : Rigid and smooth centring and shuttering for R.C.C. works including false works and dismantling them after casting including cost of materials complete in ground floor R.C.C. foundation, plinth band and footings bases of columns mass concrete precast slabs, etc			
	52.65	Square Meter	216.39264180804	11393.072591193
5	Concrete : AR0307 (Cement concrete (1:2:4)with 12mm size hard broken granite chips per 1cum) : Cement concrete work with (1:2:4) using 12mm size hard granite(crusher broken) chips including hoisting and laying in position compacting to specified design section and curing for proper period with cost conveyance, royalty, taxes of all materials, labour and T&P required for the work etc. complete as per specification and direction of Engineer-in charge.			
	1.816425	Cubic Meter	6911.27716882	12553.816631374
6	miscellaneous : ARM287 (Supplying and fixing of 80mm thick cement concrete interlocking paver block of M-40 grade of approved make, design, colour and size made by Block making machine with proper compaction laid in required pattern etc. complete in all respect conforming to IRC) : Supplying and fixing of 80mm thick cement concrete interlocking paver block of M-40 grade of approved make, design, colour and size made by Block making machine with proper compaction laid in required pattern etc. complete in all respect conforming to IRC SP-63:2018. (New miscellaneous items) and as directed by Engineer-in-Charge.			
	192.1725	Square Meter	626.9766	120487.6606635

7	Earth Work : AR0115a (Filling foundation and plinth with crusher dust well watered and rammed) : Filling foundation and plinth with crusher dust well watered and rammed including cost, conveyance, royalty, taxes of all materials, labours and T & P required for the work etc. complete and as per direction of Engineer-in charge.			
	19.21725	Cubic Meter	660.391732	12690.913011777

Total Amount:	195897.86312653
----------------------	-----------------

Provision for Contingency (+) @	2000
Display Citizen Board (+) @	2000
Any Other Lumpsum (+) @	102
Provision for survey investigation and quality control (+) @	

Total Amount:	199999.86312653
----------------------	-----------------

Grand Net Total Amount	199999.86312653
-------------------------------	-----------------

MADHU BEHERA
JE
Bhanjanagar Block

NITYANANDA PATRO
AEE
Bhanjanagar Block

BHARATEE DEVI
BDO
Bhanjanagar Block