

Estimate Abstract

**OD/358/3417/118778/424037/00065341 : Const of CC Road from KOKASARA Bazarpada to Durgamandap
Block : Kokasara, Gram Panchayat : Koksara
Created By:Kirti Ranjan Behera**

Sl No	Quantity	Unit	Rate in (Rs.)	Amount (Rs.)
1	Earth Work : AR0102aa (Earth work in hard soil or gravelly soil foundation & plinth within 50m. Initial lead and 1.5m initial lift) : Earth work in hard soil or gravelly soil foundation & plinth within 50m. Initial lead and 1.5m initial lift including rough dressing and breaking clods to maximum 5cm to 7cm and laying in layers not exceeding 0.3m in depth and as per the direction of the Engineer-in-charge			
	4	Cubic Meter	240.77592	963.10368
2	Earth Work : AR0115 (Filling foundation and plinth with sand well watered and rammed) : Filling foundation and plinth with sand well watered and rammed including cost, conveyance, royalty, taxes of all materials, labours and T & P required for the work etc. complete and as per direction of Engineer-in charge.			
	14.4	Cubic Meter	585.045732	8424.6585408
3	Concrete : AR0303 (Cement concrete (1:3:6) with 4 cm. Crusher Broken hard granite metal) : Cement concrete (1:3:6) with 4 cm. hard granite(Crusher Broken) metal including laying in layers not exceeding 300 mm in depth, ramming, compacting to proper thickness, watering and curing for proper period with cost conveyance, royalty, taxes of all materials, labour and T&P required for the work etc. complete and as per direction of Engineer-in charge.			
	18.4	Cubic Meter	5386.1517653	99105.19248152
4	R.C.C. Work : AR0410c (R.C.C. foundation , plinth band and footings bases of columns mass concrete precast slabs etc) : Rigid and smooth centring and shuttering for R.C.C. works including false works and dismantling them after casting including cost of materials complete in ground floor R.C.C. foundation, plinth band and footings bases of columns mass concrete precast slabs, etc			
	24	Square Meter	216.39264180804	5193.423403393
5	Concrete : AR0307 (Cement concrete (1:2:4)with 12mm size hard broken granite chips per 1cum) : Cement concrete work with (1:2:4) using 12mm size hard granite(crusher broken) chips including hoisting and laying in position compacting to specified design section and curing for proper period with cost conveyance, royalty, taxes of all materials, labour and T&P required for the work etc. complete as per specifaion and direction of Engineer-in charge.			
	11.52	Cubic Meter	6917.5233401	79689.868877952

Total Amount:	193376.24698366
----------------------	-----------------

Provision for Contingency (+) @	2000
Display Citizen Board (+) @	3000

Any Other Lumpsum (+) @	1623.5
Provision for survey investigation and quality control (+) @	
Total Amount:	199999.74698366
Grand Net Total Amount	199999.74698366

Kirti Ranjan Behera
JE
Kokasara Block

Sukrutanand Mishra
AEE
Kokasara Block

Dr Himanchal Majhi
BDO
Kokasara Block