

Estimate Abstract

OD/354/3380/117908/411363/00065527 : Repair & Maintenance of AWC Building at Pranadeipur under Hatiota GP

**Block : Polosara, Gram Panchayat : Hatiota
Created By:Sudhansu Sekhar Pattanaik**

Sl No	Quantity	Unit	Rate in (Rs.)	Amount (Rs.)
1	Concrete : AR0303a (Cement concrete (1:3:6) with 4 cm. hard granite(Hand Broken) metal) : Cement concrete (1:3:6) with 4 cm. hard granite(Hand Broken) metal including laying in layers not exceeding 300 mm in depth, ramming, compacting to proper thickness, watering and curing for proper period with cost conveyance, royalty, taxes of all materials, labour and T&P required for the work etc. complete and as per direction of Engineer-in charge.			
	1.6	Cubic Meter	4998.58760842	7997.740173472
2	Concrete : AR0307 (Cement concrete (1:2:4)with 12mm size hard broken granite chips per 1cum) : Cement concrete work with (1:2:4) using 12mm size hard granite(crusher broken) chips including hoisting and laying in position compacting to specified design section and curing for proper period with cost conveyance, royalty, taxes of all materials, labour and T&P required for the work etc. complete as per specifaion and direction of Engineer-in charge.			
	0.83825	Cubic Meter	6737.01992154	5647.3069492309
3	Masonry Brick Work : AR0603bi (Flyash Bricks of size (25cm x 12cm x 8cm) in cement mortar (1:6) in superstructure) : Brickwork with Flyash Bricks of size (25cm x 12cm x 8cm) in cement mortar (1:6) in superstructure having crushing strength not less than 75.00 Kg/cm2 with dimensional tolerance ±8 percent immersing the bricks in water not less than six hours with cost conveyance, royalty, taxes of all materials, labor, and T&P required for the work, etc. complete and as per direction of Engineer-in-charge.			
	0.98505	Cubic Meter	5004.381759856	4929.5662525462
4	Plastering : AR1014 (16mm thick cement Plaster in CM (1:6) over brick work in inside.) : 16mm thick cement Plaster in CM (1:6) over brick work in inside including racking out joints finishing smooth with proper plumb and line, curing for proper period with cost conveyance, royalty, taxes of all materials, labour and T & P required for the work etc comp.and as per direction of Engineer-in-charge.			
	3.24	Square Meter	241.373538414	782.05026446136

Total Amount:	19356.66363971
----------------------	----------------

Provision for PH Work (+) @	24243.33
Provision for EI Work (+) @	
Provision for Contingency (+) @	450
Display Citizen Board (+) @	500

Any Other Lumpsum (+) @	450
Provision for survey investigation and quality control (+) @	
Total Amount:	44999.99363971
Grand Net Total Amount	44999.99363971

Sudhansu Sekhar Pattanaik
JE
Polosara Block

Laxmi Narayan Pattanayak
AEE
Polosara Block

SASI BHUSAN MAHAPATRO
BDO
Polosara Block