

Estimate Abstract

**OD/358/3417/118774/424063/00065349 : Improvement of Galli Rod at Gambhariguda
Block : Kokasara, Gram Panchayat : Gambhariguda
Created By:Kirti Ranjan Behera**

Sl No	Quantity	Unit	Rate in (Rs.)	Amount (Rs.)
1	Earth Work : AR0102aa (Earth work in hard soil or gravelly soil foundation & plinth within 50m. Initial lead and 1.5m initial lift) : Earth work in hard soil or gravelly soil foundation & plinth within 50m. Initial lead and 1.5m initial lift including rough dressing and breaking clods to maximum 5cm to 7cm and laying in layers not exceeding 0.3m in depth and as per the direction of the Engineer-in-charge			
	21.58	Cubic Meter	240.77592	5195.9443536
2	Earth Work : AR0115 (Filling foundation and plinth with sand well watered and rammed) : Filling foundation and plinth with sand well watered and rammed including cost, conveyance, royalty, taxes of all materials, labours and T & P required for the work etc. complete and as per direction of Engineer-in charge.			
	53.82	Cubic Meter	585.045732	31487.16129624
3	Concrete : AR0303 (Cement concrete (1:3:6) with 4 cm. Crusher Broken hard granite metal) : Cement concrete (1:3:6) with 4 cm. hard granite(Crusher Broken) metal including laying in layers not exceeding 300 mm in depth, ramming, compacting to proper thickness, watering and curing for proper period with cost conveyance, royalty, taxes of all materials, labour and T&P required for the work etc. complete and as per direction of Engineer-in charge.			
	20.28	Cubic Meter	5399.9019558	109510.01166362
4	Concrete : AR0307 (Cement concrete (1:2:4)with 12mm size hard broken granite chips per 1cum) : Cement concrete work with (1:2:4) using 12mm size hard granite(crusher broken) chips including hoisting and laying in position compacting to specified design section and curing for proper period with cost conveyance, royalty, taxes of all materials, labour and T&P required for the work etc. complete as per specification and direction of Engineer-in charge.			
	13.104	Cubic Meter	6936.9177136	90901.369719014
5	R.C.C. Work : AR0410c (R.C.C. foundation , plinth band and footings bases of columns mass concrete precast slabs etc) : Rigid and smooth centring and shuttering for R.C.C. works including false works and dismantling them after casting including cost of materials complete in ground floor R.C.C. foundation, plinth band and footings bases of columns mass concrete precast slabs, etc			
	31.2	Square Meter	216.39264180804	6751.4504244108

Total Amount:	243845.93745689
----------------------	-----------------

Provision for Contingency (+) @	2500
Display Citizen Board (+) @	3000

Any Other Lumpsum (+) @	654
Provision for survey investigation and quality control (+) @	
Total Amount:	249999.93745689
Grand Net Total Amount	249999.93745689

Kirti Ranjan Behera
JE
Kokasara Block

Sukrutanand Mishra
AEE
Kokasara Block

Dr Himanchal Majhi
BDO
Kokasara Block