

**Estimate Abstract**

**OD/346/3304/275595/393647/00065525 : All weather connectivity of road from Incomplete CC road to Panichhatra Sasan at-Panichhatra.  
Block : Khaira, Gram Panchayat : Goliha  
Created By:Gopal Jena**

Sl No	Quantity	Unit	Rate in (Rs.)	Amount (Rs.)
1	<b>R.C.C. Work : AR0410c (R.C.C. foundation , plinth band and footings bases of columns mass concrete precast slabs etc) :</b> Rigid and smooth centring and shuttering for R.C.C. works including false works and dismantling them after casting including cost of materials complete in ground floor R.C.C. foundation, plinth band and footings bases of columns mass concrete precast slabs, etc			
	20.8	Square Meter	216.23489289764	4497.6857722709
2	<b>Earth Work : AR0102aa (Earth work in hard soil or gravelly soil foundation &amp; plinth within 50m. Initial lead and 1.5m initial lift) :</b> Earth work in hard soil or gravelly soil foundation & plinth within 50m. Initial lead and 1.5m initial lift including rough dressing and breaking clods to maximum 5cm to 7cm and laying in layers not exceeding 0.3m in depth and as per the direction of the Engineer-in-charge			
	1.755	Cubic Meter	240.77592	422.5617396
3	<b>Earth Work : AR0115 (Filling foundation and plinth with sand well watered and rammed) :</b> Filling foundation and plinth with sand well watered and rammed including cost, conveyance, royalty, taxes of all materials, labours and T & P required for the work etc. complete and as per direction of Engineer-in charge.			
	7.8	Cubic Meter	1568.331232	12232.9836096
4	<b>Concrete : AR0303a (Cement concrete (1:3:6) with 4 cm. hard granite(Hand Broken) metal) :</b> Cement concrete (1:3:6) with 4 cm. hard granite(Hand Broken) metal including laying in layers not exceeding 300 mm in depth, ramming, compacting to proper thickness, watering and curing for proper period with cost conveyance, royalty, taxes of all materials, labour and T&P required for the work etc. complete and as per direction of Engineer-in charge.			
	9.555	Cubic Meter	6800.2638147	64976.520749458
5	<b>Concrete : AR0307 (Cement concrete (1:2:4)with 12mm size hard broken granite chips per 1cum) :</b> Cement concrete work with (1:2:4) using 12mm size hard granite(crusher broken) chips including hoisting and laying in position compacting to specified design section and curing for proper period with cost conveyance, royalty, taxes of all materials, labour and T&P required for the work etc. complete as per specification and direction of Engineer-in charge.			
	7.02	Cubic Meter	8380.2034009	58829.027874318

<b>Total Amount:</b>	140958.77974525
----------------------	-----------------

Provision for Contingency (+) @	704.79389872625
---------------------------------	-----------------

Display Citizen Board (+) @	1108.42
Any Other Lumpsum (+) @	1016
Provision for survey investigation and quality control (+) @	

<b>Total Amount:</b>	143787.99364397
----------------------	-----------------

<b>Grand Net Total Amount</b>	143787.99364398
-------------------------------	-----------------

**Gopal Jena**  
**JE**  
**Khaira Block**

**Bibhuti Bhusan Nayak**  
**AEE**  
**Khaira Block**

**Narayan Sahu**  
**BDO**  
**Khaira Block**