

Estimate Abstract

**OD/359/3433/119018/416966/00066155 : Construction of c.c road at Kalsapadar
Block : Tumudibandh, Gram Panchayat : Tumudibandh
Created By:Sunil**

Sl No	Quantity	Unit	Rate in (Rs.)	Amount (Rs.)
1	Earth Work : AR0102aa (Earth work in hard soil or gravelly soil foundation & plinth within 50m. Initial lead and 1.5m initial lift) : Earth work in hard soil or gravelly soil foundation & plinth within 50m. Initial lead and 1.5m initial lift including rough dressing and breaking clods to maximum 5cm to 7cm and laying in layers not exceeding 0.3m in depth and as per the direction of the Engineer-in-charge			
	6.01732	Cubic Meter	240.77592	1448.8257589344
2	Earth Work : AR0115 (Filling foundation and plinth with sand well watered and rammed) : Filling foundation and plinth with sand well watered and rammed including cost, conveyance, royalty, taxes of all materials, labours and T & P required for the work etc. complete and as per direction of Engineer-in charge.			
	43.4208253776	Cubic Meter	579.298832	25153.63342572
3	Concrete : AR0303 (Cement concrete (1:3:6) with 4 cm. Crusher Broken hard granite metal) : Cement concrete (1:3:6) with 4 cm. hard granite(Crusher Broken) metal including laying in layers not exceeding 300 mm in depth, ramming, compacting to proper thickness, watering and curing for proper period with cost conveyance, royalty, taxes of all materials, labour and T&P required for the work etc. complete and as per direction of Engineer-in charge.			
	1.58857248	Cubic Meter	5296.85303344	8414.4349595273
4	Concrete : AR0307 (Cement concrete (1:2:4)with 12mm size hard broken granite chips per 1cum) : Cement concrete work with (1:2:4) using 12mm size hard granite(crusher broken) chips including hoisting and laying in position compacting to specified design section and curing for proper period with cost conveyance, royalty, taxes of all materials, labour and T&P required for the work etc. complete as per specification and direction of Engineer-in charge.			
	16.232322432	Cubic Meter	6841.10968728	111047.09823661
5	R.C.C. Work : AR0410c (R.C.C. foundation , plinth band and footings bases of columns mass concrete precast slabs etc) : Rigid and smooth centring and shuttering for R.C.C. works including false works and dismantling them after casting including cost of materials complete in ground floor R.C.C. foundation, plinth band and footings bases of columns mass concrete precast slabs, etc			
	55.02458884	Square Meter	216.23489289764	11898.236074554
6	miscellaneous : ARM287 (Supplying and fixing of 80mm thick cement concrete interlocking paver block of M-40 grade of approved make, design, colour and size made by Block making machine with proper compaction laid in required pattern etc. complete in all respect conforming to IRC) : Supplying and fixing of 80mm thick cement concrete interlocking paver block of M-40 grade of approved make, design, colour and size made by Block making machine with proper compaction laid in required pattern etc. complete in all respect conforming to IRC SP-63:2018. (New miscellaneous items) and as directed by Engineer-in-Charge.			
	425.06374105	Square Meter	623.8938	265194.6326459

Total Amount:	423156.86110124
----------------------	-----------------

Provision for Contingency (+) @	4231.5686110124
Display Citizen Board (+) @	5000
Any Other Lumpsum (+) @	149125
Provision for survey investigation and quality control (+) @	154.56

Total Amount:	581667.98971226
----------------------	-----------------

Grand Net Total Amount	581667.98971225
-------------------------------	-----------------

**Sunil
JE
Tumudibandh Block**

**Kedar
AEE
Tumudibandh Block**

**BANABIHARI HARAPAL
BDO
Tumudibandh Block**