

Estimate Abstract

**OD/373/3583/121676/384577/00066551 : CONSTRUCTION OF C C ROAD FROM BABUL TREE TO MANGO
PLANTATION AT JUNA BALANDA
Block : Lathikata, Gram Panchayat : Balanda
Created By:MADHUSMITA SAHU**

Sl No	Quantity	Unit	Rate in (Rs.)	Amount (Rs.)
1	Earth Work : AR0102aa (Earth work in hard soil or gravelly soil foundation & plinth within 50m. Initial lead and 1.5m initial lift) : Earth work in hard soil or gravelly soil foundation & plinth within 50m. Initial lead and 1.5m initial lift including rough dressing and breaking clods to maximum 5cm to 7cm and laying in layers not exceeding 0.3m in depth and as per the direction of the Engineer-in-charge			
	17.833	Cubic Meter	240.77592	4293.75698136
2	Earth Work : AR0115 (Filling foundation and plinth with sand well watered and rammed) : Filling foundation and plinth with sand well watered and rammed including cost, conveyance, royalty, taxes of all materials, labours and T & P required for the work etc. complete and as per direction of Engineer-in charge.			
	12.7978	Cubic Meter	581.258232	7438.8266014896
3	Concrete : AR0303 (Cement concrete (1:3:6) with 4 cm. Crusher Broken hard granite metal) : Cement concrete (1:3:6) with 4 cm. hard granite(Crusher Broken) metal including laying in layers not exceeding 300 mm in depth, ramming, compacting to proper thickness, watering and curing for proper period with cost conveyance, royalty, taxes of all materials, labour and T&P required for the work etc. complete and as per direction of Engineer-in charge.			
	17.833	Cubic Meter	5295.63406242	94437.042235136
4	R.C.C. Work : AR0410c (R.C.C. foundation , plinth band and footings bases of columns mass concrete precast slabs etc) : Rigid and smooth centring and shuttering for R.C.C. works including false works and dismantling them after casting including cost of materials complete in ground floor R.C.C. foundation, plinth band and footings bases of columns mass concrete precast slabs, etc			
	16.784	Square Meter	216.39264180804	3631.9341001061
5	Concrete : AR0307 (Cement concrete (1:2:4)with 12mm size hard broken granite chips per 1cum) : Cement concrete work with (1:2:4) using 12mm size hard granite(crusher broken) chips including hoisting and laying in position compacting to specified design section and curing for proper period with cost conveyance, royalty, taxes of all materials, labour and T&P required for the work etc. complete as per specifaicaion and direction of Engineer-in charge.			
	12.7978	Cubic Meter	6783.71151454	86816.58322078
Total Amount:				196618.14313887
Provision for Contingency (+) @				310

Display Citizen Board (+) @	4000
Any Other Lumpsum (+) @	990
Provision for survey investigation and quality control (+) @	

Total Amount:	201918.14313887
----------------------	-----------------

Grand Net Total Amount	201918.14313887
-------------------------------	-----------------

MADHUSMITA SAHU
JE
Lathikata Block

LASA MARANDI
AEE
Lathikata Block

BDO LATHIKATA
BDO
Lathikata Block