

Estimate Abstract

**OD/360/3441/119227/395717/00066604 : CONSTRUCTION OF HUMP PIPE CULVERT AT DALIKANDA
PLAYGROUND ROAD**

**Block : Rajkanika, Gram Panchayat : Siko
Created By:RAJASMITA BARIK**

Sl No	Quantity	Unit	Rate in (Rs.)	Amount (Rs.)
1	Earth Work : AR0102aa (Earth work in hard soil or gravelly soil foundation & plinth within 50m. Initial lead and 1.5m initial lift) : Earth work in hard soil or gravelly soil foundation & plinth within 50m. Initial lead and 1.5m initial lift including rough dressing and breaking clods to maximum 5cm to 7cm and laying in layers not exceeding 0.3m in depth and as per the direction of the Engineer-in-charge			
	45.9864832	Cubic Meter	240.77592	11072.437800045
2	Earth Work : AR0115 (Filling foundation and plinth with sand well watered and rammed) : Filling foundation and plinth with sand well watered and rammed including cost, conveyance, royalty, taxes of all materials, labours and T & P required for the work etc. complete and as per direction of Engineer-in charge.			
	40.491324992	Cubic Meter	901.872632	36518.017843702
3	Concrete : AR0303 (Cement concrete (1:3:6) with 4 cm. Crusher Broken hard granite metal) : Cement concrete (1:3:6) with 4 cm. hard granite(Crusher Broken) metal including laying in layers not exceeding 300 mm in depth, ramming, compacting to proper thickness, watering and curing for proper period with cost conveyance, royalty, taxes of all materials, labour and T&P required for the work etc. complete and as per direction of Engineer-in charge.			
	22.91253872	Cubic Meter	6479.38838626	148459.2372821
4	Masonry Brick Work : AR0603b (Flyash Bricks of size (25cm x 12cm x 8cm) in cement mortar (1:6) in foundation and plinth) : Brickwork with Flyash Bricks of size (25cm x 12cm x 8cm) in cement mortar (1:6) in foundation and plinth having crushing strength not less than 75.00 Kg/cm ² with dimensional tolerance ±8 percent immersing the bricks in water not less than six hours with cost conveyance, royalty, taxes of all materials, labor, and T&P required for the work, etc. complete and as per direction of Engineer-in-charge.			
	3.6245504	Cubic Meter	5737.524257668	20795.94584314
5	Concrete : AR0307 (Cement concrete (1:2:4)with 12mm size hard broken granite chips per 1cum) : Cement concrete work with (1:2:4) using 12mm size hard granite(crusher broken) chips including hoisting and laying in position compacting to specified design section and curing for proper period with cost conveyance, royalty, taxes of all materials, labour and T&P required for the work etc. complete as per specification and direction of Engineer-in charge.			
	11.68068	Cubic Meter	7956.97105362	92942.832646598
6	Plastering : AR1014i (16mm thick cement Plaster in CM (1:6) over brick work in outside (outside)) : 16mm thick cement Plaster in CM (1:6) over brick work in outside including racking out joints finishing smooth with proper plumb and line, curing for proper period with cost conveyance, royalty, taxes of all materials, labour and T & P required for the work etc comp.and as per direction of Engineer-in-charge.			
	14.86448	Square Meter	247.875305142	3684.5375157772

7	R.C.C. Work : AR0410c (R.C.C. foundation , plinth band and footings bases of columns mass concrete precast slabs etc) : Rigid and smooth centring and shuttering for R.C.C. works including false works and dismantling them after casting including cost of materials complete in ground floor R.C.C. foundation, plinth band and footings bases of columns mass concrete precast slabs, etc			
	16.165122	Square Meter	216.23489289764	3495.4634243473

Total Amount:	316968.47235571
----------------------	-----------------

Provision for Contingency (+) @	3714
Display Citizen Board (+) @	1000
Any Other Lumpsum (+) @	49760
Provision for survey investigation and quality control (+) @	

Total Amount:	371442.47235571
----------------------	-----------------

Grand Net Total Amount	371442.47235571
-------------------------------	-----------------

RAJASMITA BARIK
JE
Rajkanika Block

SUDHANSU SEKHAR PATRA
AEE
Rajkanika Block

KAILASH CHANDRA MAHALIK
BDO
Rajkanika Block