

Estimate Abstract

**OD/366/3515/275423/427528/00065610 : Construction of VSS Building Kadamali of Ichhapur GP
Block : Jhorigam, Gram Panchayat : Ichhapur
Created By:Sri Kranti Kumar Pattanayak**

Sl No	Quantity	Unit	Rate in (Rs.)	Amount (Rs.)
1	Earth Work : AR0102aa (Earth work in hard soil or gravelly soil foundation & plinth within 50m. Initial lead and 1.5m initial lift) : Earth work in hard soil or gravelly soil foundation & plinth within 50m. Initial lead and 1.5m initial lift including rough dressing and breaking clods to maximum 5cm to 7cm and laying in layers not exceeding 0.3m in depth and as per the direction of the Engineer-in-charge			
	33.3327	Cubic Meter	240.77592	8025.711508584
2	Earth Work : AR0115 (Filling foundation and plinth with sand well watered and rammed) : Filling foundation and plinth with sand well watered and rammed including cost, conveyance, royalty, taxes of all materials, labours and T & P required for the work etc. complete and as per direction of Engineer-in charge.			
	24.6356	Cubic Meter	693.034932	17073.331370779
3	Concrete : AR0303 (Cement concrete (1:3:6) with 4 cm. Crusher Broken hard granite metal) : Cement concrete (1:3:6) with 4 cm. hard granite(Crusher Broken) metal including laying in layers not exceeding 300 mm in depth, ramming, compacting to proper thickness, watering and curing for proper period with cost conveyance, royalty, taxes of all materials, labour and T&P required for the work etc. complete and as per direction of Engineer-in charge.			
	17.03245	Cubic Meter	5438.0287993	92622.953622637
4	Concrete : AR0307 (Cement concrete (1:2:4)with 12mm size hard broken granite chips per 1cum) : Cement concrete work with (1:2:4) using 12mm size hard granite(crusher broken) chips including hoisting and laying in position compacting to specified design section and curing for proper period with cost conveyance, royalty, taxes of all materials, labour and T&P required for the work etc. complete as per specification and direction of Engineer-in charge.			
	1.50875	Cubic Meter	6957.8658711	10497.680133022
5	R.C.C. Work : AR0404A (Reinforced cement concrete work of M-20 grade with 20mm & down grade size black hard crusher broken granite chips) : Reinforced cement concrete work of M-20 grade with 20mm & down grade size black hard crusher broken granite chips including hoisting and laying in position compacting to specified design section and curing for proper period with cost conveyance, royalty,taxes of all materials, labour and T&P required for the work etc. complete and as per direction of Engineer-in charge. (excluding centring and shuttering)			
	15.561587	Cubic Meter	5622.216871681	87490.616981532
6	R.C.C. Work : AR0409 (Supplying, fitting, and placing uncoated HYSD bar reinforcement including labor charges for cutting, bending, binding, and tying the grills and placing in position) : Supplying, fitting, and placing uncoated HYSD bar reinforcement including labor charges for cutting, bending, binding, and tying the grills and placing in position including cost of binding wire 18 to 20 gauge with cost of steel rod and as per drawing, design, and direction of Engineer-in-charge.			
	15.5	Quintal	8430.7391448	130676.4567444

7	R.C.C. Work : AR0410c (R.C.C. foundation , plinth band and footings bases of columns mass concrete precast slabs etc) : Rigid and smooth centring and shuttering for R.C.C. works including false works and dismantling them after casting including cost of materials complete in ground floor R.C.C. foundation, plinth band and footings bases of columns mass concrete precast slabs, etc			
	61.0908	Square Meter	216.55039071844	13229.236609302
8	R.C.C. Work : AR0410e (Rigid and smooth centering and shuttering for R.C.C. works including false works and dismantling them after casting) : Rigid and smooth centring and shuttering for R.C.C. works including false works and dismantling them after casting including cost of materials complete in ground floor R.C.C. Lintels Data for 7.8 sqm			
	10.302	Square Meter	500.00130144795	5151.0134075168
9	R.C.C. Work : AR0410b (centering and shuttering fRigid and smooth or R.C.C. works including false works and dismantling them after casting) : Rigid and smooth centring and shuttering for R.C.C. works including false works and dismantling them after casting including cost of materials complete in ground floor R.C.C. stairs excluding landing but including railing details for 5 Sqm			
	8.6625	Square Meter	919.009696506	7960.9214959832
10	R.C.C. Work : AR0410d (Rigid and smooth centering and shuttering for R.C.C. works including false works and dismantling them after casting) : Rigid and smooth centring and shuttering for R.C.C. works including false works and dismantling them after casting including cost of materials complete in ground floor R.C.C. beams, column, grider and bressmer, etc. Data for 4.2sqm			
	36.5884	Square Meter	1048.4253517895	38360.206141415
11	R.C.C. Work : AR0410a (Centring & Shuttering for R.C.C. floor and roof slabs, landings,balconies, projecting sun shades and chajjas) : Rigid and smooth centring and shuttering for R.C.C. works including false works and dismantling them after casting including cost of materials complete in ground floor R.C.C. floor and roof slabs, landings, balconies, projecting sun shades and chajjas up to 4.3m height			
	51.2174	Square Meter	663.90898015022	34003.691799946
12	Masonry Brick Work : AR0603di (C.B. Bricks of size (25cm x 12cm x 8cm) in cement mortar (1:4) in superstructure) : Brickwork with C.B. Bricks of size (25cm x 12cm x 8cm) in cement mortar (1:6) in superstructure having crushing strength not less than 75.00 Kg/cm ² with dimensional tolerance ±8 percent immersing the bricks in water not less than six hours with cost conveyance, royalty, taxes of all materials, labor, and T&P required for the work, etc. complete and as per direction of Engineer-in-charge.			
	24.834825	Cubic Meter	4991.394043	123960.39756395
13	Plastering : AR1004 (12mm thick cement plster (1:6) over Brick work in inside) : 12mm thick cement plster (1:6) over Brick work in inside including racking out joints finishing smooth with proper plumb and line curing for proper period with cost conveyance, royalty, taxes of all materials, labour and T & P required for the work etc. comp.and as per direction of Engineer-in-charge.			
	102.3433	Square Meter	170.317128806	17430.817008531
14	Plastering : AR1014 (16mm thick cement Plaster in CM (1:6) over brick work in inside.) : 16mm thick cement Plaster in CM (1:6) over brick work in inside including racking out joints finishing smooth with proper plumb and line, curing for proper period with cost conveyance, royalty, taxes of all materials, labour and T & P required for the work etc comp.and as per direction of Engineer-in-charge.			

112.29	Square Meter	244.66334031	27473.24648341
15	Other Building Items. : AR1901B (Vitrified Tile 600mmx600mm Plain Ivory) : Supplying, fitting & fixing Vitrified Tile 600mmx600mm Plain Ivory in floors of size 600mm x 600 mm of approved make conforming IS:13755 laid on 20 mm thick cement mortar(1:4)and filling joints with white cement of approved quality including cost of all materials, taxes, labour, T&P , etc. required for the work all complete as per direction of Engineer-in-charge(for new work only)		
	35.425	Square Meter	1009.880238341
16	Painting : AR0918c (Finishing wall with two coat water proofing cement paint including one coat cement wash on the outer surface of approved shade on new work (Outside)) : Finishing wall with two coat water proofing cement paint including one coat cement wash on the outer surface of approved shade on new work to give an even shade including all costs of labour, Paint, Brushes, and putty required for the work, etc. complete and as per direction of Engineer-in-charge. (Outside)		
	85.6125	Square Meter	57.890317259086
17	Other Building Items. : AR1902 (cement based wall putty (water based)) : Finishing surface of walls with cement based wall putty (water based) of approved make and finished smooth and even surface to receive painting including cost of scaffolding staging charges with cost of all materials taxes,labour,T&P,etc.complete. and as per the direction of Engineer in Charge.		
	147.715	Square Meter	79.21834
18	Painting : AR0920 (Finishing wall two coats with plastic emulsion paint of approved shades on new work (Inside)) : Finishing wall two coats with plastic emulsion paint of approved shades on new work to give an even shade including all costs of labor, Paint and Brushes required for the work, etc. complete and as per direction of the Engineer-in-charge.(Inside)		
	147.715	Square Meter	94.7676397125
19	Iron Work : AR1704 (Iron Doors and windows fixing) : Supplying, fitting & fixing of Mild steel and put up for frames & shutters of Doors and windows fixing in position with cost, conveyance, taxes of all materials, labours and T & P required for the work etc. as per direction of Engineer-in-charge.		
	3.2655	Quintal	15773.439083087
20	Painting : AR0901b (Priming one coat in inner surface with primer of approved quality over iron work.) : Priming one coat in inner surface with primer of approved quality over iron work including cost conveyance, taxes of all materials, labor and T&P required for the work complete as per direction of the Engineer-in-charge.		
	23.8725	Square Meter	65.84406247451
21	Other Building Items. : AR1911 (Stainless steel of 304 grade in hand railing using 50mm dia of 2mm) : Supplying, fitting and fixing of Stainless steel of 304 grade in hand railing using 50mm dia of 2mm thick circular pipe with Balustrade of size 32mm x 32mm x 2mm @ 0.90mtr. C/C and stainless square pipe bracing of size 32mm x 32mm x 2mm in 3 rows in staircase as per approved design and specification, buffing, polishing etc with cost,conveyance, taxes of all materials, labour,T&P etc. required for the complete in all respect. and as per direction of Engineer in Charge		
	8.25	Meter	3129.0244276074

Total Amount:	759282.24132882
----------------------	-----------------

Provision for PH Work (+) @	30000
Provision for EI Work (+) @	30000
Provision for Contingency (+) @	8500
Display Citizen Board (+) @	4500
Any Other Lumpsum (+) @	17717
Provision for survey investigation and quality control (+) @	

Total Amount:	849999.24132882
----------------------	-----------------

Grand Net Total Amount	849999.24132882
-------------------------------	-----------------

Sri Kranti Kumar Pattanayak
JE
Jhorigam Block

Bineet Kumar Mishra
AEE
Jhorigam Block

MADHUSUDAN MAJHI
BDO
Jhorigam Block