

Estimate Abstract

**OD/356/3401/275216/400817/00067200 : repair and maintenance of Ochninda primary school
Block : Korei, Gram Panchayat : Patharapada
Created By:Smitasri Dash**

Sl No	Quantity	Unit	Rate in (Rs.)	Amount (Rs.)
1	Earth Work : AR0102aa (Earth work in hard soil or gravelly soil foundation & plinth within 50m. Initial lead and 1.5m initial lift) : Earth work in hard soil or gravelly soil foundation & plinth within 50m. Initial lead and 1.5m initial lift including rough dressing and breaking clods to maximum 5cm to 7cm and laying in layers not exceeding 0.3m in depth and as per the direction of the Engineer-in-charge			
	15.5304	Cubic Meter	240.77592	3739.346347968
2	Earth Work : AR0115 (Filling foundation and plinth with sand well watered and rammed) : Filling foundation and plinth with sand well watered and rammed including cost, conveyance, royalty, taxes of all materials, labours and T & P required for the work etc. complete and as per direction of Engineer-in charge.			
	2.496	Cubic Meter	817.598232	2040.725187072
3	Concrete : AR0303 (Cement concrete (1:3:6) with 4 cm. Crusher Broken hard granite metal) : Cement concrete (1:3:6) with 4 cm. hard granite(Crusher Broken) metal including laying in layers not exceeding 300 mm in depth, ramming, compacting to proper thickness, watering and curing for proper period with cost conveyance, royalty, taxes of all materials, labour and T&P required for the work etc. complete and as per direction of Engineer-in charge.			
	2.496	Cubic Meter	6009.54804166	14999.831911983
4	R.C.C. Work : AR0404Aa (Reinforced cement concrete work of M-20 grade with 20mm & down grade size black hard crusher broken granite chips) : Reinforced cement concrete work of M-20 grade with 20mm & down grade size black hard crusher broken granite chips including hoisting and laying in position compacting to specified design section and curing for proper period with cost conveyance, royalty,taxes of all materials, labour and T&P required for the work etc. (including centring and shuttering) complete and as per direction of Engineer-in charge (RCC foundation, footing bases of column, mass concrete, pre-cast slabs etc.)			
	3.11184	Cubic Meter	6546.9304272047	20372.999980593
5	R.C.C. Work : AR0404Ab (Reinforced cement concrete work of M-20 grade with 20mm & down grade size black hard crusher broken granite chips) : Reinforced cement concrete work of M-20 grade with 20mm & down grade size black hard crusher broken granite chips including hoisting and laying in position compacting to specified design section and curing for proper period with cost conveyance, royalty,taxes of all materials, labour and T&P required for the work etc. (including centring and shuttering) complete and as per direction of Engineer-in charge (RCC Plinth band)			
	1.6155	Cubic Meter	7303.7525523464	11799.212248316
6	R.C.C. Work : AR0404Ac (Reinforced cement concrete work of M-20 grade with 20mm & down grade size black hard crusher broken granite chips) : Reinforced cement concrete work of M-20 grade with 20mm & down grade size black hard crusher broken granite chips including hoisting and laying in position compacting to specified design section and curing for proper period with cost conveyance, royalty,taxes of all materials, labour and T&P required for the work etc. (including centring and shuttering) complete and as per direction of Engineer-in charge. (RCC Beams, Column, Girder & Bressmer etc)			

2.95376	Cubic Meter	14602.683814525	43132.677317153
7	R.C.C. Work : AR0409 (Supplying, fitting, and placing uncoated HYSD bar reinforcement including labor charges for cutting, bending, binding, and tying the grills and placing in position) : Supplying, fitting, and placing uncoated HYSD bar reinforcement including labor charges for cutting, bending, binding, and tying the grills and placing in position including cost of binding wire 18 to 20 gauge with cost of steel rod and as per drawing, design, and direction of Engineer-in-charge.		
6.11864	Quintal	8429.867838	51579.3265483

Total Amount:	147664.11954139
----------------------	-----------------

Provision for PH Work (+) @	
Provision for EI Work (+) @	
Provision for Contingency (+) @	738.32059770695
Display Citizen Board (+) @	1597
Any Other Lumpsum (+) @	
Provision for survey investigation and quality control (+) @	

Total Amount:	149999.44013909
----------------------	-----------------

Grand Net Total Amount	149999.4401391
-------------------------------	----------------

Smitasri Dash
JE
Korei Block

SWAGAT KUMAR DASH
AEE
Korei Block

Abanikanta Sahoo
BDO
Korei Block