

Estimate Abstract

OD/361/3452/119469/385961/00068146 : CONST OF CC ROAD FROM RASIK MAHANTA HOUSE TO JAGDISH NAIK HOUSE

Block : Kendujhar Sadar, Gram Panchayat : Raikala

Created By:Ranjan Kumar Swain

Sl No	Quantity	Unit	Rate in (Rs.)	Amount (Rs.)
1	Earth Work : AR0102aa (Earth work in hard soil or gravelly soil foundation & plinth within 50m. Initial lead and 1.5m initial lift) : Earth work in hard soil or gravelly soil foundation & plinth within 50m. Initial lead and 1.5m initial lift including rough dressing and breaking clods to maximum 5cm to 7cm and laying in layers not exceeding 0.3m in depth and as per the direction of the Engineer-in-charge			
	1.7698	Cubic Meter	240.77592	426.125223216
2	Earth Work : AR0115 (Filling foundation and plinth with sand well watered and rammed) : Filling foundation and plinth with sand well watered and rammed including cost, conveyance, royalty, taxes of all materials, labours and T & P required for the work etc. complete and as per direction of Engineer-in charge.			
	7.71915968	Cubic Meter	1238.929832	9563.4972055236
3	Concrete : AR0303 (Cement concrete (1:3:6) with 4 cm. Crusher Broken hard granite metal) : Cement concrete (1:3:6) with 4 cm. hard granite(Crusher Broken) metal including laying in layers not exceeding 300 mm in depth, ramming, compacting to proper thickness, watering and curing for proper period with cost conveyance, royalty, taxes of all materials, labour and T&P required for the work etc. complete and as per direction of Engineer-in charge.			
	16.52249884	Cubic Meter	6370.70753624	105260.0078775
4	Concrete : AR0307 (Cement concrete (1:2:4)with 12mm size hard broken granite chips per 1cum) : Cement concrete work with (1:2:4) using 12mm size hard granite(crusher broken) chips including hoisting and laying in position compacting to specified design section and curing for proper period with cost conveyance, royalty, taxes of all materials, labour and T&P required for the work etc. complete as per specification and direction of Engineer-in charge.			
	34.227932	Cubic Meter	7809.96749888	267319.03647387
5	R.C.C. Work : AR0410c (R.C.C. foundation , plinth band and footings bases of columns mass concrete precast slabs etc) : Rigid and smooth centring and shuttering for R.C.C. works including false works and dismantling them after casting including cost of materials complete in ground floor R.C.C. foundation, plinth band and footings bases of columns mass concrete precast slabs, etc			
	39.8089355	Square Meter	216.23489289764	8608.0809042116
Total Amount:				391176.74768433
Provision for Contingency (+) @				4000

Display Citizen Board (+) @	3000
Any Other Lumpsum (+) @	1823.25
Provision for survey investigation and quality control (+) @	

Total Amount:	399999.99768433
----------------------	-----------------

Grand Net Total Amount	399999.99768433
-------------------------------	-----------------

Ranjan Kumar Swain
JE
Kendujhar Sadar Block

Sabyasachi Pradhan
AEE
Kendujhar Sadar Block

Binod Chandra Panda
BDO
Kendujhar Sadar Block