

**Estimate Abstract**

**OD/361/3452/119450/386056/00068117 : CONST. OF CC/PAVER ROAD FROM KUSAPADA RD ROAD TO GURU  
CH. MAHANTA HOUSE  
Block : Kendujhar Sadar, Gram Panchayat : Bauripada  
Created By:Ratikanta Lenka**

Sl No	Quantity	Unit	Rate in (Rs.)	Amount (Rs.)
1	<b>Earth Work : AR0102aa (Earth work in hard soil or gravelly soil foundation &amp; plinth within 50m. Initial lead and 1.5m initial lift) :</b> Earth work in hard soil or gravelly soil foundation & plinth within 50m. Initial lead and 1.5m initial lift including rough dressing and breaking clods to maximum 5cm to 7cm and laying in layers not exceeding 0.3m in depth and as per the direction of the Engineer-in-charge			
	5.687712448	Cubic Meter	240.77592	1369.4641973627
2	<b>Earth Work : AR0115 (Filling foundation and plinth with sand well watered and rammed) :</b> Filling foundation and plinth with sand well watered and rammed including cost, conveyance, royalty, taxes of all materials, labours and T & P required for the work etc. complete and as per direction of Engineer-in charge.			
	22.493780437947	Cubic Meter	995.055232	22382.553912238
3	<b>Concrete : AR0303 (Cement concrete (1:3:6) with 4 cm. Crusher Broken hard granite metal) :</b> Cement concrete (1:3:6) with 4 cm. hard granite(Crusher Broken) metal including laying in layers not exceeding 300 mm in depth, ramming, compacting to proper thickness, watering and curing for proper period with cost conveyance, royalty, taxes of all materials, labour and T&P required for the work etc. complete and as per direction of Engineer-in charge.			
	35.375546762901	Cubic Meter	5970.31247874	211203.0682808
4	<b>Concrete : AR0307 (Cement concrete (1:2:4)with 12mm size hard broken granite chips per 1cum) :</b> Cement concrete work with (1:2:4) using 12mm size hard granite(crusher broken) chips including hoisting and laying in position compacting to specified design section and curing for proper period with cost conveyance, royalty, taxes of all materials, labour and T&P required for the work etc. complete as per specification and direction of Engineer-in charge.			
	20.041923111505	Cubic Meter	7441.10070238	149133.96814207
5	<b>R.C.C. Work : AR0410c (R.C.C. foundation , plinth band and footings bases of columns mass concrete precast slabs etc) :</b> Rigid and smooth centring and shuttering for R.C.C. works including false works and dismantling them after casting including cost of materials complete in ground floor R.C.C. foundation, plinth band and footings bases of columns mass concrete precast slabs, etc			
	37.32099316	Square Meter	216.23489289764	8070.1009587862

<b>Total Amount:</b>	392159.15549125
----------------------	-----------------

Provision for Contingency (+) @	4000
---------------------------------	------

Display Citizen Board (+) @	3000
Any Other Lumpsum (+) @	840.75
Provision for survey investigation and quality control (+) @	

<b>Total Amount:</b>	399999.90549125
----------------------	-----------------

<b>Grand Net Total Amount</b>	399999.90549125
-------------------------------	-----------------

**Ratikanta Lenka**  
**JE**  
**Kendujhar Sadar Block**

**Sabyasachi Pradhan**  
**AEE**  
**Kendujhar Sadar Block**

**Binod Chandra Panda**  
**BDO**  
**Kendujhar Sadar Block**