

**Estimate Abstract**

**OD/346/3305/116241/393323/00068470 : repair and restoration of road from tala roudina sital house to bijay house**

**Block : Nilgiri, Gram Panchayat : K.C.Pur**

**Created By:BAIDYANATH SINGH**

Sl No	Quantity	Unit	Rate in (Rs.)	Amount (Rs.)
1	<b>R.C.C. Work : AR0401 (R.C.C work) :</b> 'Reinforced cement concrete (1:2:4) work with 12mm size black hard crusher broken granite chips including hoisting and laying in position compacting to specified design section and curing for proper period with cost conveyance, royalty,taxes of all materials, labour and T&P required for the work etc. complete and as per direction of Engineer-in charge. (To be used for minor repair work only)			
	7.3906848	Cubic Meter	7836.6986861	57918.569861539
2	<b>R.C.C. Work : AR0410c (R.C.C. foundation , plinth band and footings bases of columns mass concrete precast slabs etc) :</b> Rigid and smooth centring and shuttering for R.C.C. works including false works and dismantling them after casting including cost of materials complete in ground floor R.C.C. foundation, plinth band and footings bases of columns mass concrete precast slabs, etc			
	4.8495366	Square Meter	216.23489289764	1048.6390273042

<b>Total Amount:</b>	58967.208888843
----------------------	-----------------

Provision for Contingency (+) @	540
Display Citizen Board (+) @	492
Any Other Lumpsum (+) @	
Provision for survey investigation and quality control (+) @	

<b>Total Amount:</b>	59999.208888843
----------------------	-----------------

<b>Grand Net Total Amount</b>	59999.208888843
-------------------------------	-----------------

**BAIDYANATH SINGH**  
JE  
Nilgiri Block

**Sarat kumar Upadhyay**  
AEE  
Nilgiri Block

**Bikram Kishore Parida**  
BDO  
Nilgiri Block