

Estimate Abstract

**OD/365/3496/120177/388479/00066812 : Construction of CC Road in Sansialinai village under Durdura GP
Block : Joshipur, Gram Panchayat : Durdura
Created By:PRAJAPATI SI**

Sl No	Quantity	Unit	Rate in (Rs.)	Amount (Rs.)
1	Earth Work : AR0102aa (Earth work in hard soil or gravelly soil foundation & plinth within 50m. Initial lead and 1.5m initial lift) : Earth work in hard soil or gravelly soil foundation & plinth within 50m. Initial lead and 1.5m initial lift including rough dressing and breaking clods to maximum 5cm to 7cm and laying in layers not exceeding 0.3m in depth and as per the direction of the Engineer-in-charge			
	3.8	Cubic Meter	240.77592	914.948496
2	Earth Work : AR0115 (Filling foundation and plinth with sand well watered and rammed) : Filling foundation and plinth with sand well watered and rammed including cost, conveyance, royalty, taxes of all materials, labours and T & P required for the work etc. complete and as per direction of Engineer-in charge.			
	10.716	Cubic Meter	1392.480132	14921.817094512
3	Concrete : AR0303 (Cement concrete (1:3:6) with 4 cm. Crusher Broken hard granite metal) : Cement concrete (1:3:6) with 4 cm. hard granite(Crusher Broken) metal including laying in layers not exceeding 300 mm in depth, ramming, compacting to proper thickness, watering and curing for proper period with cost conveyance, royalty, taxes of all materials, labour and T&P required for the work etc. complete and as per direction of Engineer-in charge.			
	14.136	Cubic Meter	6378.7058333	90169.385659529
4	R.C.C. Work : AR0410c (R.C.C. foundation , plinth band and footings bases of columns mass concrete precast slabs etc) : Rigid and smooth centring and shuttering for R.C.C. works including false works and dismantling them after casting including cost of materials complete in ground floor R.C.C. foundation, plinth band and footings bases of columns mass concrete precast slabs, etc			
	15.2	Square Meter	216.55039071844	3291.5659389203
5	Concrete : AR0307 (Cement concrete (1:2:4)with 12mm size hard broken granite chips per 1cum) : Cement concrete work with (1:2:4) using 12mm size hard granite(crusher broken) chips including hoisting and laying in position compacting to specified design section and curing for proper period with cost conveyance, royalty, taxes of all materials, labour and T&P required for the work etc. complete as per specifaion and direction of Engineer-in charge.			
	11.096	Cubic Meter	7900.4214041	87663.075899894

Total Amount:	196960.79308885
----------------------	-----------------

Provision for Contingency (+) @	1000
Display Citizen Board (+) @	2000

Any Other Lumpsum (+) @	39
Provision for survey investigation and quality control (+) @	0

Total Amount:	199999.79308885
----------------------	-----------------

Grand Net Total Amount	199999.79308885
-------------------------------	-----------------

PRAJAPATI SI
JE
Joshipur Block

HEMANTA KUMAR NAIK
AEE
Joshipur Block

MADHAB CHANDRA BIRUA
BDO
Joshipur Block