

Estimate Abstract

**OD/365/3496/120177/388481/00066809 : Construction of CC Road at Durdura Maroda Sahi under Durdura GP
Block : Joshipur, Gram Panchayat : Durdura
Created By:PRAJAPATI SI**

| SI No | Quantity | Unit | Rate in (Rs.) | Amount (Rs.) |
|-------|--|--------------|-----------------|-----------------|
| 1 | Earth Work : AR0102aa (Earth work in hard soil or gravelly soil foundation & plinth within 50m. Initial lead and 1.5m initial lift) : Earth work in hard soil or gravelly soil foundation & plinth within 50m. Initial lead and 1.5m initial lift including rough dressing and breaking clods to maximum 5cm to 7cm and laying in layers not exceeding 0.3m in depth and as per the direction of the Engineer-in-charge | | | |
| | 3.78125 | Cubic Meter | 240.77592 | 910.4339475 |
| 2 | Earth Work : AR0115 (Filling foundation and plinth with sand well watered and rammed) : Filling foundation and plinth with sand well watered and rammed including cost, conveyance, royalty, taxes of all materials, labours and T & P required for the work etc. complete and as per direction of Engineer-in charge. | | | |
| | 11.7975 | Cubic Meter | 1326.729132 | 15652.08693477 |
| 3 | R.C.C. Work : AR0410c (R.C.C. foundation , plinth band and footings bases of columns mass concrete precast slabs etc) : Rigid and smooth centring and shuttering for R.C.C. works including false works and dismantling them after casting including cost of materials complete in ground floor R.C.C. foundation, plinth band and footings bases of columns mass concrete precast slabs, etc | | | |
| | 12.1 | Square Meter | 216.55039071844 | 2620.2597276931 |
| 4 | Concrete : AR0303a (Cement concrete (1:3:6) with 4 cm. hard granite(Hand Broken) metal) : Cement concrete (1:3:6) with 4 cm. hard granite(Hand Broken) metal including laying in layers not exceeding 300 mm in depth, ramming, compacting to proper thickness, watering and curing for proper period with cost conveyance, royalty, taxes of all materials, labour and T&P required for the work etc. complete and as per direction of Engineer-in charge. | | | |
| | 14.06625 | Cubic Meter | 6145.5752093 | 86445.197287816 |
| 5 | Concrete : AR0307a (First floor) : Cement concrete work with (1:2:4) using 12mm size hard granite(hand broken) chips including hoisting and laying in position compacting to proper thickness and curing for proper period with cost conveyance, royalty, taxes of all materials, labour and T&P required for the work etc. complete as per specifaicaon and direction of Engineer-in charge. | | | |
| | 11.04125 | Cubic Meter | 7967.6086241 | 87972.358720844 |

| | |
|----------------------|-----------------|
| Total Amount: | 193600.33661862 |
|----------------------|-----------------|

| | |
|---------------------------------|---------|
| Provision for Contingency (+) @ | 2000 |
| Display Citizen Board (+) @ | 3899.66 |

| | |
|--|-----|
| Any Other Lumpsum (+) @ | 500 |
| Provision for survey investigation and quality control (+) @ | 0 |

| | |
|----------------------|-----------------|
| Total Amount: | 199999.99661862 |
|----------------------|-----------------|

| | |
|-------------------------------|-----------------|
| Grand Net Total Amount | 199999.99661862 |
|-------------------------------|-----------------|

PRAJAPATI SI
JE
Joshipur Block

HEMANTA KUMAR NAIK
AEE
Joshipur Block

MADHAB CHANDRA BIRUA
BDO
Joshipur Block