

Estimate Abstract

**OD/363/3476/275171/429940/00067946 : CC with Paver Block road at Panua
Block : Nandapur, Gram Panchayat : K Hinbar
Created By:Prasanna Kumar Suchen**

Sl No	Quantity	Unit	Rate in (Rs.)	Amount (Rs.)
1	Earth Work : AR0102aa (Earth work in hard soil or gravelly soil foundation & plinth within 50m. Initial lead and 1.5m initial lift) : Earth work in hard soil or gravelly soil foundation & plinth within 50m. Initial lead and 1.5m initial lift including rough dressing and breaking clods to maximum 5cm to 7cm and laying in layers not exceeding 0.3m in depth and as per the direction of the Engineer-in-charge			
	13.643	Cubic Meter	240.77592	3284.90587656
2	Earth Work : AR0115 (Filling foundation and plinth with sand well watered and rammed) : Filling foundation and plinth with sand well watered and rammed including cost, conveyance, royalty, taxes of all materials, labours and T & P required for the work etc. complete and as per direction of Engineer-in charge.			
	18.875	Cubic Meter	848.302232	16011.704629
3	Concrete : AR0307 (Cement concrete (1:2:4)with 12mm size hard broken granite chips per 1cum) : Cement concrete work with (1:2:4) using 12mm size hard granite(crusher broken) chips including hoisting and laying in position compacting to specified design section and curing for proper period with cost conveyance, royalty, taxes of all materials, labour and T&P required for the work etc. complete as per specifaion and direction of Engineer-in charge.			
	19.3935	Cubic Meter	7412.5175226	143754.65857454
4	Concrete : AR0303 (Cement concrete (1:3:6) with 4 cm. Crusher Broken hard granite metal) : Cement concrete (1:3:6) with 4 cm. hard granite(Crusher Broken) metal including laying in layers not exceeding 300 mm in depth, ramming, compacting to proper thickness, watering and curing for proper period with cost conveyance, royalty, taxes of all materials, labour and T&P required for the work etc. complete and as per direction of Engineer-in charge.			
	1.75	Cubic Meter	5920.7676418	10361.34337315
5	miscellaneous : ARM287 (Supplying and fixing of 80mm thick cement concrete interlocking paver block of M-40 grade of approved make, design, colour and size made by Block making machine with proper compaction laid in required pattern etc. complete in all respect conforming to IRC) : Supplying and fixing of 80mm thick cement concrete interlocking paver block of M-40 grade of approved make, design, colour and size made by Block making machine with proper compaction laid in required pattern etc. complete in all respect conforming to IRC SP-63:2018. (New miscellaneous items) and as directed by Engineer-in-Charge.			
	180	Square Meter	631.884	113739.12
6	R.C.C. Work : AR0410c (R.C.C. foundation , plinth band and footings bases of columns mass concrete precast slabs etc) : Rigid and smooth centring and shuttering for R.C.C. works including false works and dismantling them after casting including cost of materials complete in ground floor R.C.C. foundation, plinth band and footings bases of columns mass concrete precast slabs, etc			
	24.26	Square Meter	217.02363744964	5264.9934445283

Total Amount:	292416.72589778
----------------------	-----------------

Provision for Contingency (+) @	3000
Display Citizen Board (+) @	4583
Any Other Lumpsum (+) @	
Provision for survey investigation and quality control (+) @	

Total Amount:	299999.72589778
----------------------	-----------------

Grand Net Total Amount	299999.72589778
-------------------------------	-----------------

Prasanna Kumar Suchen
JE
Nandapur Block

JHASKETAN BEHERA
AEE
Nandapur Block

DURGA PRASADA DORA
BDO
Nandapur Block