

Estimate Abstract

**OD/365/3505/120325/390135/00063155 : Const. of CC road from Sumanta Mohanty house to PMGSY road,
Rasgobindpur
Block : Rasgovindpur, Gram Panchayat : Rasgovindpur
Created By:DIPAK KUMAR MURMU**

Sl No	Quantity	Unit	Rate in (Rs.)	Amount (Rs.)
1	Earth Work : AR0110 (Fine dressing of earth work in ordinary or hard soil in road formation) : Fine dressing of earth work in ordinary or hard soil in road formaton according to the direction of the department including cutting or filling earth upto 0.15m depth of surface.			
	108.69651	Square Meter	4.6662	507.199654962
2	Earth Work : AR0102aa (Earth work in hard soil or gravelly soil foundation & plinth within 50m. Initial lead and 1.5m initial lift) : Earth work in hard soil or gravelly soil foundation & plinth within 50m. Initial lead and 1.5m initial lift including rough dressing and breaking clods to maximum 5cm to 7cm and laying in layers not exceeding 0.3m in depth and as per the direction of the Engineer-in-charge			
	2.4847992	Cubic Meter	240.77592	598.27981339526
3	Earth Work : AR0115 (Filling foundation and plinth with sand well watered and rammed) : Filling foundation and plinth with sand well watered and rammed including cost, conveyance, royalty, taxes of all materials, labours and T & P required for the work etc. complete and as per direction of Engineer-in charge.			
	10.088284752	Cubic Meter	931.526232	9397.5018823736
4	Concrete : AR0303 (Cement concrete (1:3:6) with 4 cm. Crusher Broken hard granite metal) : Cement concrete (1:3:6) with 4 cm. hard granite(Crusher Broken) metal including laying in layers not exceeding 300 mm in depth, ramming, compacting to proper thickness, watering and curing for proper period with cost conveyance, royalty, taxes of all materials, labour and T&P required for the work etc. complete and as per direction of Engineer-in charge.			
	14.262747408	Cubic Meter	6485.8877403	92506.578556543
5	Concrete : AR0307 (Cement concrete (1:2:4)with 12mm size hard broken granite chips per 1cum) : Cement concrete work with (1:2:4) using 12mm size hard granite(crusher broken) chips including hoisting and laying in position compacting to specified design section and curing for proper period with cost conveyance, royalty, taxes of all materials, labour and T&P required for the work etc. complete as per specifaion and direction of Engineer-in charge.			
	10.93311648	Cubic Meter	7987.8973021	87332.611634137
6	R.C.C. Work : AR0410c (R.C.C. foundation , plinth band and footings bases of columns mass concrete precast slabs etc) : Rigid and smooth centring and shuttering for R.C.C. works including false works and dismantling them after casting including cost of materials complete in ground floor R.C.C. foundation, plinth band and footings bases of columns mass concrete precast slabs, etc			
	34.13070414	Square Meter	216.23489289764	7380.2491542339

Total Amount:	197722.42069564
----------------------	-----------------

Provision for Contingency (+) @	1977.2242069564
Display Citizen Board (+) @	2219.35
Any Other Lumpsum (+) @	
Provision for survey investigation and quality control (+) @	

Total Amount:	201918.9949026
----------------------	----------------

Grand Net Total Amount	201918.9949026
-------------------------------	----------------

DIPAK KUMAR MURMU
JE
Rasgovindpur Block

ANUPAM PRAKASH BEHERA
AEE
Rasgovindpur Block

ANANTA KUMAR HANSDA
BDO
Rasgovindpur Block