

**Estimate Abstract**

**OD/356/3397/118350/401377/00070471 : Construction Of Paver Road From Rd Road To Jayadeba Jata House  
Block : Dharmasala, Gram Panchayat : Marjitapur  
Created By:SMRUTIREKHA DHADA**

Sl No	Quantity	Unit	Rate in (Rs.)	Amount (Rs.)
1	<b>Earth Work : AR0102aa (Earth work in hard soil or gravelly soil foundation &amp; plinth within 50m. Initial lead and 1.5m initial lift) :</b> Earth work in hard soil or gravelly soil foundation & plinth within 50m. Initial lead and 1.5m initial lift including rough dressing and breaking clods to maximum 5cm to 7cm and laying in layers not exceeding 0.3m in depth and as per the direction of the Engineer-in-charge			
	19.95	Cubic Meter	240.77592	4803.479604
2	<b>Earth Work : AR0115 (Filling foundation and plinth with sand well watered and rammed) :</b> Filling foundation and plinth with sand well watered and rammed including cost, conveyance, royalty, taxes of all materials, labours and T & P required for the work etc. complete and as per direction of Engineer-in charge.			
	90.44	Cubic Meter	721.547232	65256.73166208
3	<b>Concrete : AR0303 (Cement concrete (1:3:6) with 4 cm. Crusher Broken hard granite metal) :</b> Cement concrete (1:3:6) with 4 cm. hard granite(Crusher Broken) metal including laying in layers not exceeding 300 mm in depth, ramming, compacting to proper thickness, watering and curing for proper period with cost conveyance, royalty, taxes of all materials, labour and T&P required for the work etc. complete and as per direction of Engineer-in charge.			
	39.9	Cubic Meter	5548.13132936	221370.44004146
4	<b>miscellaneous : ARM287 (Supplying and fixing of 80mm thick cement concrete interlocking paver block of M-40 grade of approved make, design, colour and size made by Block making machine with proper compaction laid in required pattern etc. complete in all respect conforming to IRC) :</b> Supplying and fixing of 80mm thick cement concrete interlocking paver block of M-40 grade of approved make, design, colour and size made by Block making machine with proper compaction laid in required pattern etc. complete in all respect conforming to IRC SP-63:2018. (New miscellaneous items) and as directed by Engineer-in-Charge.			
	837.9	Square Meter	628.119	526300.9101
5	<b>R.C.C. Work : AR0410c (R.C.C. foundation , plinth band and footings bases of columns mass concrete precast slabs etc) :</b> Rigid and smooth centring and shuttering for R.C.C. works including false works and dismantling them after casting including cost of materials complete in ground floor R.C.C. foundation, plinth band and footings bases of columns mass concrete precast slabs, etc			
	319.2	Square Meter	216.23489289764	69022.177812927

<b>Total Amount:</b>	886753.73922047
----------------------	-----------------

Provision for Contingency (+) @	9000
---------------------------------	------

Display Citizen Board (+) @	4246
Any Other Lumpsum (+) @	
Provision for survey investigation and quality control (+) @	

<b>Total Amount:</b>	899999.73922047
----------------------	-----------------

<b>Grand Net Total Amount</b>	899999.73922047
-------------------------------	-----------------

**SMRUTIREKHA DHADA**  
**JE**  
**Dharmasala Block**

**LINGARAJ PANDA**  
**AEE**  
**Dharmasala Block**

**Jyotirmaya Kar**  
**BDO**  
**Dharmasala Block**