

Estimate Abstract

**OD/356/3397/118359/401400/00070474 : Construction Of Concrete Road From Lunibara Laxmidhara Pradhan House To Pond
Block : Dharmasala, Gram Panchayat : Sahanidiha
Created By:SMRUTIREKHA DHADA**

Sl No	Quantity	Unit	Rate in (Rs.)	Amount (Rs.)
1	Earth Work : AR0102aa (Earth work in hard soil or gravelly soil foundation & plinth within 50m. Initial lead and 1.5m initial lift) : Earth work in hard soil or gravelly soil foundation & plinth within 50m. Initial lead and 1.5m initial lift including rough dressing and breaking clods to maximum 5cm to 7cm and laying in layers not exceeding 0.3m in depth and as per the direction of the Engineer-in-charge			
	7.05	Cubic Meter	240.77592	1697.470236
2	Earth Work : AR0115 (Filling foundation and plinth with sand well watered and rammed) : Filling foundation and plinth with sand well watered and rammed including cost, conveyance, royalty, taxes of all materials, labours and T & P required for the work etc. complete and as per direction of Engineer-in charge.			
	25.85	Cubic Meter	787.298232	20351.6592972
3	Concrete : AR0303 (Cement concrete (1:3:6) with 4 cm. Crusher Broken hard granite metal) : Cement concrete (1:3:6) with 4 cm. hard granite(Crusher Broken) metal including laying in layers not exceeding 300 mm in depth, ramming, compacting to proper thickness, watering and curing for proper period with cost conveyance, royalty, taxes of all materials, labour and T&P required for the work etc. complete and as per direction of Engineer-in charge.			
	37.6	Cubic Meter	5546.69135216	208555.59484122
4	Concrete : AR0307 (Cement concrete (1:2:4)with 12mm size hard broken granite chips per 1cum) : Cement concrete work with (1:2:4) using 12mm size hard granite(crusher broken) chips including hoisting and laying in position compacting to specified design section and curing for proper period with cost conveyance, royalty, taxes of all materials, labour and T&P required for the work etc. complete as per specification and direction of Engineer-in charge.			
	28.2	Cubic Meter	7071.52064792	199416.88227134
5	R.C.C. Work : AR0410c (R.C.C. foundation , plinth band and footings bases of columns mass concrete precast slabs etc) : Rigid and smooth centring and shuttering for R.C.C. works including false works and dismantling them after casting including cost of materials complete in ground floor R.C.C. foundation, plinth band and footings bases of columns mass concrete precast slabs, etc			
	56.4	Square Meter	216.23489289764	12195.647959427
Total Amount:				442217.25460519
Provision for Contingency (+) @				4500

Display Citizen Board (+) @	3282
Any Other Lumpsum (+) @	
Provision for survey investigation and quality control (+) @	

Total Amount:	449999.25460519
----------------------	-----------------

Grand Net Total Amount	449999.25460519
-------------------------------	-----------------

SMRUTIREKHA DHADA
JE
Dharmasala Block

LINGARAJ PANDA
AEE
Dharmasala Block

Jyotirmaya Kar
BDO
Dharmasala Block