

Estimate Abstract

**OD/373/3584/121702/383637/00068541 : Construction of Cement Concrete Road from Prymary School to
Awnganwadi at Budapahad
Block : Lephripara, Gram Panchayat : Masabira
Created By:Santosh Tandia**

Sl No	Quantity	Unit	Rate in (Rs.)	Amount (Rs.)
1	Earth Work : AR0102aa (Earth work in hard soil or gravelly soil foundation & plinth within 50m. Initial lead and 1.5m initial lift) : Earth work in hard soil or gravelly soil foundation & plinth within 50m. Initial lead and 1.5m initial lift including rough dressing and breaking clods to maximum 5cm to 7cm and laying in layers not exceeding 0.3m in depth and as per the direction of the Engineer-in-charge			
	5.7375	Cubic Meter	240.77592	1381.451841
2	Earth Work : AR0115 (Filling foundation and plinth with sand well watered and rammed) : Filling foundation and plinth with sand well watered and rammed including cost, conveyance, royalty, taxes of all materials, labours and T & P required for the work etc. complete and as per direction of Engineer-in charge.			
	17.4675	Cubic Meter	975.764232	17044.16172246
3	Concrete : AR0303 (Cement concrete (1:3:6) with 4 cm. Crusher Broken hard granite metal) : Cement concrete (1:3:6) with 4 cm. hard granite(Crusher Broken) metal including laying in layers not exceeding 300 mm in depth, ramming, compacting to proper thickness, watering and curing for proper period with cost conveyance, royalty, taxes of all materials, labour and T&P required for the work etc. complete and as per direction of Engineer-in charge.			
	23.205	Cubic Meter	5667.82235502	131521.81774824
4	R.C.C. Work : AR0410c (R.C.C. foundation , plinth band and footings bases of columns mass concrete precast slabs etc) : Rigid and smooth centring and shuttering for R.C.C. works including false works and dismantling them after casting including cost of materials complete in ground floor R.C.C. foundation, plinth band and footings bases of columns mass concrete precast slabs, etc			
	30.6	Square Meter	216.23489289764	6616.7877226678
5	Concrete : AR0307 (Cement concrete (1:2:4)with 12mm size hard broken granite chips per 1cum) : Cement concrete work with (1:2:4) using 12mm size hard granite(crusher broken) chips including hoisting and laying in position compacting to specified design section and curing for proper period with cost conveyance, royalty, taxes of all materials, labour and T&P required for the work etc. complete as per specifaicaion and direction of Engineer-in charge.			
	18.615	Cubic Meter	7140.44232274	132919.33383781
Total Amount:				289483.55287217
Provision for Contingency (+) @				3000

Display Citizen Board (+) @	5000
Any Other Lumpsum (+) @	2516.44
Provision for survey investigation and quality control (+) @	

Total Amount:	299999.99287217
----------------------	-----------------

Grand Net Total Amount	299999.99287217
-------------------------------	-----------------

Santosh Tandia
JE
Lephripara Block

Brusabhanu Bhoi
AEE
Lephripara Block

BDO LEPHRIPARA
BDO
Lephripara Block