

Estimate Abstract

**OD/346/3302/116158/391834/00071318 : CONSTRUCTION OF CC ROAD FROM KHAIRDA ADB ROAD TO S.K
RAJUDDIN HOUSE VIA S,K GYASUDDINN
Block : Bhogra, Gram Panchayat : Kosabakamarda
Created By:SOUMITA MOHANTY**

Sl No	Quantity	Unit	Rate in (Rs.)	Amount (Rs.)
1	Earth Work : AR0102aa (Earth work in hard soil or gravelly soil foundation & plinth within 50m. Initial lead and 1.5m initial lift) : Earth work in hard soil or gravelly soil foundation & plinth within 50m. Initial lead and 1.5m initial lift including rough dressing and breaking clods to maximum 5cm to 7cm and laying in layers not exceeding 0.3m in depth and as per the direction of the Engineer-in-charge			
	6.204777216	Cubic Meter	240.77592	1493.9609425774
2	Earth Work : AR0115 (Filling foundation and plinth with sand well watered and rammed) : Filling foundation and plinth with sand well watered and rammed including cost, conveyance, royalty, taxes of all materials, labours and T & P required for the work etc. complete and as per direction of Engineer-in charge.			
	6.204777216	Cubic Meter	1005.761232	6240.5243770497
3	Concrete : AR0303 (Cement concrete (1:3:6) with 4 cm. Crusher Broken hard granite metal) : Cement concrete (1:3:6) with 4 cm. hard granite(Crusher Broken) metal including laying in layers not exceeding 300 mm in depth, ramming, compacting to proper thickness, watering and curing for proper period with cost conveyance, royalty, taxes of all materials, labour and T&P required for the work etc. complete and as per direction of Engineer-in charge.			
	6.204777216	Cubic Meter	6834.6749187	42407.635214316
4	R.C.C. Work : AR0410c (R.C.C. foundation , plinth band and footings bases of columns mass concrete precast slabs etc) : Rigid and smooth centring and shuttering for R.C.C. works including false works and dismantling them after casting including cost of materials complete in ground floor R.C.C. foundation, plinth band and footings bases of columns mass concrete precast slabs, etc			
	5.16633583	Square Meter	216.23489289764	1117.1420748733
5	R.C.C. Work : AR0401 (R.C.C work) : 'Reinforced cement concrete (1:2:4) work with 12mm size black hard crusher broken granite chips including hoisting and laying in position compacting to specified design section and curing for proper period with cost conveyance, royalty,taxes of all materials, labour and T&P required for the work etc. complete and as per direction of Engineer-in charge. (To be used for minor repair work only)			
	5.452683008	Cubic Meter	8223.4918009	44840.094009195

Total Amount:	96099.356618012
----------------------	-----------------

Provision for Contingency (+) @	500
Display Citizen Board (+) @	2500

Any Other Lumpsum (+) @	900
Provision for survey investigation and quality control (+) @	

Total Amount:	99999.356618012
----------------------	-----------------

Grand Net Total Amount	99999.356618012
-------------------------------	-----------------

SOUMITA MOHANTY
JE
Bhograi Block

PRAMOD KUMAR BEHERA
AEE
Bhograi Block

Prasanta Kumar Moharana
BDO
Bhograi Block