

Estimate Abstract

**OD/346/3305/116250/393098/00071183 : repair and restoration of road from Ania singh house to mukhi sahi
Block : Nilgiri, Gram Panchayat : Radhakishorepur
Created By: Bharat Singh**

Sl No	Quantity	Unit	Rate in (Rs.)	Amount (Rs.)
1	Concrete : AR0307 (First floor) : Cement concrete work with (1:2:4) using 12mm size hard granite(crusher broken) chips including hoisting and laying in position compacting to specified design section and curing for proper period with cost conveyance, royalty, taxes of all materials, labour and T&P required for the work etc. complete as per specifaicaion and direction of Engineer-in charge.			
	7.22927904	Cubic Meter	8134.0927114	58803.625947941
2	R.C.C. Work : AR0410c (R.C.C. foundation , plinth band and footings bases of columns mass concrete precast slabs etc) : Rigid and smooth centring and shuttering for R.C.C. works including false works and dismantling them after casting including cost of materials complete in ground floor R.C.C. foundation, plinth band and footings bases of columns mass concrete precast slabs, etc			
	4.0823807872	Square Meter	216.23489289764	882.75317228758

Total Amount:	59686.379120228
----------------------	-----------------

Provision for Contingency (+) @	200
Display Citizen Board (+) @	113
Any Other Lumpsum (+) @	
Provision for survey investigation and quality control (+) @	

Total Amount:	59999.379120228
----------------------	-----------------

Grand Net Total Amount	59999.379120228
-------------------------------	-----------------

Bharat Singh
JE
Nilgiri Block

Sarat kumar Upadhyay
AEE
Nilgiri Block

Bikram Kishore Parida
BDO
Nilgiri Block