

Estimate Abstract

**OD/365/3488/120072/387531/00067633 : Repairing of AWC building at Dalsora
Block : Bahalda, Gram Panchayat : Bhitaramda
Created By:PRAFULLA KUMAR BED**

Sl No	Quantity	Unit	Rate in (Rs.)	Amount (Rs.)
1	Dismantling : AR1620 (Dismantling and removing 2.5 cm thick grading concrete from roof) : Dismantling and removing 2.5 cm thick grading concrete from roof slab cleaning the surface lowering and removing the debris within 50m lead and as per direction of Engineer-in-Charge.			
	58.52889	Square Meter	112.89193548387	6607.4396738225
2	Concrete : AR0318 (4cm thick grading concrete (1:2:4) on roof slab with 12mm size hard granite chips (Crusher Broken)) : 4cm thick grading concrete (1:2:4) on roof slab with 12mm size hard granite chips (Crusher Broken) including hoisting and laying in position compacting and curing for the proper period with cost conveyance, royalty, taxes of all materials, labor and T&P required for the work etc. complete as per specifaicaon and direction of Engineer-in charge. (Old Work)			
	58.52889	Square Meter	744.303499479	43563.257647621
3	Dismantling : AR1612 (Dismantling and removing 2.5 cm. thick artificial stone flooring) : Dismantling and removing 2.5 cm. thick artificial stone flooring including stacking the useful materials for reuse and removing the debris within 50m lead and as per direction of Engineer-in-Charge.			
	52.6388398	Square Meter	100.34838709677	5282.2226725753
4	Concrete : AR0304 (Cement concrete (1:4:8) with 4 cm. hard granite(Crusher Broken) metal) : Cement concrete (1:4:8) with 4 cm. hard granite(Crusher Broken) metal including laying in layers not exceeding 300 mm in depth, ramming, compacting to proper thickness, watering and curing for proper period with cost conveyance, royalty, taxes of all materials, labour and T&P required for the work etc. complete and as per direction of Engineer-in charge.			
	5.2946186304	Cubic Meter	5079.3865964	26893.414904303
5	Other Building Items. : AR1901B (Vitrified Tile 600mmx600mm Plain Ivory) : Supplying, fitting & fixing Vitrified Tile 600mmx600mm Plain Ivory in floors of size 600mm x 600 mm of approved make conforming IS:13755 laid on 20 mm thick cement mortar(1:4)and filling joints with white cement of approved quality including cost of all materials, taxes, labour, T&P , etc. required for the work all complete as per direction of Engineer-in-charge(for new work only)			
	53.7536758	Square Meter	1016.476858411	54639.367505227
6	Flooring : AR0817aa (Fixing Vitrified tiles of premium grade having thickness 8mm to 10mm confirming to IS 13756 of size 600mmx600mm plain (Ivory) in dados skirting and risers of steps on 12mm thick cement plaster (1:3)) : Fixing Vitrified tiles of premium grade having thickness 8mm to 10mm confirming to IS 13756 of size 600mmx600mm plain (Ivory) in dados skirting and risers of steps on 12mm thick cement plaster (1:3) jointed with neat cement slurry mixed with pigments to match the shade of the Vitrified tiles including rubbing and polishing complete including cost of precast tiles.			
	4.3939031268	Square Meter	1539.873790756	6766.0562640802

7	Plastering : AR1004 (12mm thick cement plaster (1:6) over Brick work in inside) : 12mm thick cement plaster (1:6) over Brick work in inside including racking out joints finishing smooth with proper plumb and line curing for proper period with cost conveyance, royalty, taxes of all materials, labour and T & P required for the work etc. comp.and as per direction of Engineer-in-charge.			
	22.52711944	Square Meter	171.491473986	3863.2089174243
8	Plastering : AR1014 (16mm thick cement Plaster in CM (1:6) over brick work in inside.) : 16mm thick cement Plaster in CM (1:6) over brick work in inside including racking out joints finishing smooth with proper plumb and line, curing for proper period with cost conveyance, royalty, taxes of all materials, labour and T & P required for the work etc comp.and as per direction of Engineer-in-charge.			
	94.83445337	Square Meter	246.07479511	23336.368682392
9	Painting : AR0920 (Finishing wall two coats with plastic emulsion paint of approved shades on new work (Inside)) : Finishing wall two coats with plastic emulsion paint of approved shades on new work to give an even shade including all costs of labor, Paint and Brushes required for the work, etc. complete and as per direction of the Engineer-in-charge.(Inside)			
	100.28	Square Meter	94.775145275	9504.051568177
10	Painting : AR0918cb (Finishing wall two coats with weather coat with one coat waterbound Primer) : Finishing wall two coats with weather coat with one coat waterbound Primer including all costs of labour, Paint, Primer, Brushes and putty required for the work etc. complete and as per direction of Engineer-in-charge.(Outside)			
	72.77556505	Square Meter	160.75408487694	11698.969361015
11	Painting : AR0903i (Painting two coats of enamel paint in outer surface paint (outer surface)) : Painting two coats of enamel paint in outer surface paint including all costs of labour, Paint and brushes required for the work etc. complete and as per direction of Engineer-in-charge.(Outside)			
	29.5896055	Square Meter	164.25024333952	4860.0999036954

Total Amount:	197014.45710033
----------------------	-----------------

Provision for PH Work (+) @	
Provision for EI Work (+) @	
Provision for Contingency (+) @	2023
Display Citizen Board (+) @	2500
Any Other Lumpsum (+) @	500
Provision for survey investigation and quality control (+) @	

Total Amount:	202037.45710033
----------------------	-----------------

Grand Net Total Amount	202037.45710033
-------------------------------	-----------------

PRAFULLA KUMAR BED
JE
Bahalda Block

MADAN MOHAN NAIK
AEE
Bahalda Block

MayurbhanjBahaldaBDO
BDO
Bahalda Block