

Estimate Abstract

**OD/361/3452/119471/386009/00066941 : Const of CC Road from RD Road to Ranjeisuni Sala at Teranti
Block : Kendujhar Sadar, Gram Panchayat : Sankiri
Created By:Ratikanta Lenka**

Sl No	Quantity	Unit	Rate in (Rs.)	Amount (Rs.)
1	Earth Work : AR0102aa (Earth work in hard soil or gravelly soil foundation & plinth within 50m. Initial lead and 1.5m initial lift) : Earth work in hard soil or gravelly soil foundation & plinth within 50m. Initial lead and 1.5m initial lift including rough dressing and breaking clods to maximum 5cm to 7cm and laying in layers not exceeding 0.3m in depth and as per the direction of the Engineer-in-charge			
	5.64070656	Cubic Meter	240.77592	1358.146311434
2	Earth Work : AR0115 (Filling foundation and plinth with sand well watered and rammed) : Filling foundation and plinth with sand well watered and rammed including cost, conveyance, royalty, taxes of all materials, labours and T & P required for the work etc. complete and as per direction of Engineer-in charge.			
	22.9127369376	Cubic Meter	1053.089832	24129.170292277
3	Concrete : AR0303 (Cement concrete (1:3:6) with 4 cm. Crusher Broken hard granite metal) : Cement concrete (1:3:6) with 4 cm. hard granite(Crusher Broken) metal including laying in layers not exceeding 300 mm in depth, ramming, compacting to proper thickness, watering and curing for proper period with cost conveyance, royalty, taxes of all materials, labour and T&P required for the work etc. complete and as per direction of Engineer-in charge.			
	33.40389046656	Cubic Meter	6075.04023724	202929.97866471
4	Concrete : AR0307 (Cement concrete (1:2:4)with 12mm size hard broken granite chips per 1cum) : Cement concrete work with (1:2:4) using 12mm size hard granite(crusher broken) chips including hoisting and laying in position compacting to specified design section and curing for proper period with cost conveyance, royalty, taxes of all materials, labour and T&P required for the work etc. complete as per specification and direction of Engineer-in charge.			
	19.896728728	Cubic Meter	7545.78654588	150136.46794277
5	R.C.C. Work : AR0410c (R.C.C. foundation , plinth band and footings bases of columns mass concrete precast slabs etc) : Rigid and smooth centring and shuttering for R.C.C. works including false works and dismantling them after casting including cost of materials complete in ground floor R.C.C. foundation, plinth band and footings bases of columns mass concrete precast slabs, etc			
	61.9848816	Square Meter	216.23489289764	13403.294234049

Total Amount:	391957.05744524
----------------------	-----------------

Provision for Contingency (+) @	4000
Display Citizen Board (+) @	2823

Any Other Lumpsum (+) @	1219.94
Provision for survey investigation and quality control (+) @	
Total Amount:	399999.99744524
Grand Net Total Amount	399999.99744524

Ratikanta Lenka
JE
Kendujhar Sadar Block

Sabyasachi Pradhan
AEE
Kendujhar Sadar Block

Binod Chandra Panda
BDO
Kendujhar Sadar Block