

Estimate Abstract

**OD/363/3468/119738/428262/00069547 : CONSTRUCTION OF C.C ROAD & DRAIN AT PURUNA JHILIMILI OF
BORIGUMMA
Block : Borigungumma, Gram Panchayat : Borigungumma
Created By:RATINDRA PANIGRAHI**

Sl No	Quantity	Unit	Rate in (Rs.)	Amount (Rs.)
1	Earth Work : AR0102aa (Earth work in hard soil or gravelly soil foundation & plinth within 50m. Initial lead and 1.5m initial lift) : Earth work in hard soil or gravelly soil foundation & plinth within 50m. Initial lead and 1.5m initial lift including rough dressing and breaking clods to maximum 5cm to 7cm and laying in layers not exceeding 0.3m in depth and as per the direction of the Engineer-in-charge			
	55.08	Cubic Meter	240.77592	13261.9376736
2	Earth Work : AR0115 (Filling foundation and plinth with sand well watered and rammed) : Filling foundation and plinth with sand well watered and rammed including cost, conveyance, royalty, taxes of all materials, labours and T & P required for the work etc. complete and as per direction of Engineer-in charge.			
	26.52	Cubic Meter	815.881232	21637.17027264
3	Concrete : AR0303 (Cement concrete (1:3:6) with 4 cm. Crusher Broken hard granite metal) : Cement concrete (1:3:6) with 4 cm. hard granite(Crusher Broken) metal including laying in layers not exceeding 300 mm in depth, ramming, compacting to proper thickness, watering and curing for proper period with cost conveyance, royalty, taxes of all materials, labour and T&P required for the work etc. complete and as per direction of Engineer-in charge.			
	54.06	Cubic Meter	5466.6129103	295525.09393082
4	R.C.C. Work : AR0410c (R.C.C. foundation , plinth band and footings bases of columns mass concrete precast slabs etc) : Rigid and smooth centring and shuttering for R.C.C. works including false works and dismantling them after casting including cost of materials complete in ground floor R.C.C. foundation, plinth band and footings bases of columns mass concrete precast slabs, etc			
	265.2	Square Meter	216.55039071844	57429.16361853
5	Concrete : AR0307 (Cement concrete (1:2:4)with 12mm size hard broken granite chips per 1cum) : Cement concrete work with (1:2:4) using 12mm size hard granite(crusher broken) chips including hoisting and laying in position compacting to specified design section and curing for proper period with cost conveyance, royalty, taxes of all materials, labour and T&P required for the work etc. complete as per specifaicaion and direction of Engineer-in charge.			
	15.096	Cubic Meter	6967.2367521	105177.4060097

Total Amount:	493030.77150529
----------------------	-----------------

Provision for Contingency (+) @	4930.3077150529
---------------------------------	-----------------

Display Citizen Board (+) @	2038
Any Other Lumpsum (+) @	
Provision for survey investigation and quality control (+) @	

Total Amount:	499999.07922034
----------------------	-----------------

Grand Net Total Amount	499999.07922034
-------------------------------	-----------------

RATINDRA PANIGRAHI
JE
Borigumma Block

Prakash Kumar Pradhan
AEE
Borigumma Block

SUKANTA KUMAR PATNAIK
BDO
Borigumma Block