

Estimate Abstract

**OD/365/3488/120073/387546/00067634 : Repair & Restoration of Bhaludihi AWC building
Block : Bahalda, Gram Panchayat : Gambharia
Created By:PRAFULLA KUMAR BED**

Sl No	Quantity	Unit	Rate in (Rs.)	Amount (Rs.)
1	Dismantling : AR1620 (Dismantling and removing 2.5 cm thick grading concrete from roof) : Dismantling and removing 2.5 cm thick grading concrete from roof slab cleaning the surface lowering and removing the debris within 50m lead and as per direction of Engineer-in-Charge.			
	54.27857775	Square Meter	112.89193548387	6127.6136975092
2	Concrete : AR0318 (4cm thick grading concrete (1:2:4) on roof slab with 12mm size hard granite chips (Crusher Broken)) : 4cm thick grading concrete (1:2:4) on roof slab with 12mm size hard granite chips (Crusher Broken) including hoisting and laying in position compacting and curing for the proper period with cost conveyance, royalty, taxes of all materials, labor and T&P required for the work etc. complete as per specifaicaon and direction of Engineer-in charge. (Old Work)			
	54.27857775	Square Meter	748.399866165	40622.080323727
3	Dismantling : AR1612 (Dismantling and removing 2.5 cm. thick artificial stone flooring) : Dismantling and removing 2.5 cm. thick artificial stone flooring including stacking the useful materials for reuse and removing the debris within 50m lead and as per direction of Engineer-in-Charge.			
	39.483775	Square Meter	100.34838709677	3962.1331377418
4	Concrete : AR0304 (Cement concrete (1:4:8) with 4 cm. hard granite(Crusher Broken) metal) : Cement concrete (1:4:8) with 4 cm. hard granite(Crusher Broken) metal including laying in layers not exceeding 300 mm in depth, ramming, compacting to proper thickness, watering and curing for proper period with cost conveyance, royalty, taxes of all materials, labour and T&P required for the work etc. complete and as per direction of Engineer-in charge.			
	3.9714312	Cubic Meter	5184.511194	20589.929512601
5	Plastering : AR1004 (12mm thick cement plster (1:6) over Brick work in inside) : 12mm thick cement plster (1:6) over Brick work in inside including racking out joints finishing smooth with proper plumb and line curing for proper period with cost conveyance, royalty, taxes of all materials, labour and T & P required for the work etc. comp.and as per direction of Engineer-in-charge.			
	219.57159535	Square Meter	171.97196371	37760.158427277
6	Plastering : AR1014 (16mm thick cement Plaster in CM (1:6) over brick work in inside.) : 16mm thick cement Plaster in CM (1:6) over brick work in inside including racking out joints finishing smooth with proper plumb and line, curing for proper period with cost conveyance, royalty, taxes of all materials, labour and T & P required for the work etc comp.and as per direction of Engineer-in-charge.			
	90.13913575	Square Meter	246.65147885	22232.951134998

7	Painting : AR0920 (Finishing wall two coats with plastic emulsion paint of approved shades on new work (Inside)) : Finishing wall two coats with plastic emulsion paint of approved shades on new work to give an even shade including all costs of labor, Paint and Brushes required for the work, etc. complete and as per direction of the Engineer-in-charge.(Inside)
	8.37427642 Square Meter 94.7706419375 793.63555208547
8	Painting : AR0918cb (Finishing wall two coats with weather coat with one coat waterbound Primer) : Finishing wall two coats with weather coat with one coat waterbound Primer including all costs of labour, Paint, Primer, Brushes and putty required for the work etc. complete and as per direction of Engineer-in-charge.(Outside)
	74.955533945 Square Meter 160.74632751492 12048.826808579
9	Painting : AR0903i (Painting two coats of enamel paint in outer surface paint (outer surface)) : Painting two coats of enamel paint in outer surface paint including all costs of labour, Paint and brushes required for the work etc. complete and as per direction of Engineer-in-charge.(Outside)
	22.7670414375 Square Meter 164.24574000202 3739.3895685588
10	Other Building Items. : AR1901B (Vitrified Tile 600mmx600mm Plain Ivory) : Supplying, fitting & fixing Vitrified Tile 600mmx600mm Plain Ivory in floors of size 600mm x 600 mm of approved make conforming IS:13755 laid on 20 mm thick cement mortar(1:4)and filling joints with white cement of approved quality including cost of all materials, taxes, labour, T&P , etc. required for the work all complete as per direction of Engineer-in-charge(for new work only)
	39.483775 Square Meter 1016.222452137 40124.298650126
11	Flooring : AR0817ac (Fixing Vitrified industrial Tile of premium grade having thickness 8mm to 10mm confirming to IS 4457 of size 300mmx300mm in dados skirting and risers of steps on 12mm thick cement plaster (1:3)) : Fixing Vitrified industrial Tile of premium grade having thickness 8mm to 10mm confirming to IS 4457 of size 300mmx300mm in dados skirting and risers of steps on 12mm thick cement plaster (1:3) jointed with neat cement slurry mixed with pigments to match the shade of the Vitrified tiles including rubbing and polishing complete including cost of precast tiles.
	3.86290674 Square Meter 1466.149589772 5663.5991321785

Total Amount:	193664.61594538
----------------------	-----------------

Provision for PH Work (+) @	
Provision for EI Work (+) @	
Provision for Contingency (+) @	4000
Display Citizen Board (+) @	3500
Any Other Lumpsum (+) @	873
Provision for survey investigation and quality control (+) @	

Total Amount:	202037.61594538
----------------------	-----------------

Grand Net Total Amount	202037.61594538
-------------------------------	-----------------

PRAFULLA KUMAR BED
JE
Bahalda Block

MADAN MOHAN NAIK
AEE
Bahalda Block

MayurbhanjBahaldaBDO
BDO
Bahalda Block