

Estimate Abstract

**OD/353/3361/275054/413962/00070769 : Construction of CC road at Buripadar Badasahi in convergence with MGNREGA
Block : Nuagada, Gram Panchayat : Sundardanga
Created By: Sarbeswar Sahu**

Sl No	Quantity	Unit	Rate in (Rs.)	Amount (Rs.)
1	Earth Work : AR0103a (Earth work in stoney earth and gravels mixed with stone and boulder not exceeding 0.014cum in volume within 50m. Initial lead and 1.5m initial lift) : Earth work in stoney earth and gravels mixed with stone and boulder not exceeding 0.014cum in volume within 50m. Initial lead and 1.5m initial lift including rough dressing and breaking clods to maximum 5cm to 7cm and laying in layer not exceeding 0.3m in depth and as per specification approved by the department			
	27.96124	Cubic Meter	312.915372	8749.5018161813
2	Earth Work : AR0115 (Filling foundation and plinth with sand well watered and rammed) : Filling foundation and plinth with sand well watered and rammed including cost, conveyance, royalty, taxes of all materials, labours and T & P required for the work etc. complete and as per direction of Engineer-in charge.			
	14.6376	Cubic Meter	1375.825232	20138.779415923
3	Concrete : AR0303 (Cement concrete (1:3:6) with 4 cm. Crusher Broken hard granite metal) : Cement concrete (1:3:6) with 4 cm. hard granite(Crusher Broken) metal including laying in layers not exceeding 300 mm in depth, ramming, compacting to proper thickness, watering and curing for proper period with cost conveyance, royalty, taxes of all materials, labour and T&P required for the work etc. complete and as per direction of Engineer-in charge.			
	21.13464	Cubic Meter	6292.21166742	132983.62839472
4	Concrete : AR0307 (Cement concrete (1:2:4)with 12mm size hard broken granite chips per 1cum) : Cement concrete work with (1:2:4) using 12mm size hard granite(crusher broken) chips including hoisting and laying in position compacting to specified design section and curing for proper period with cost conveyance, royalty, taxes of all materials, labour and T&P required for the work etc. complete as per specifaion and direction of Engineer-in charge.			
	15.622	Cubic Meter	7785.70797154	121628.3299314
5	R.C.C. Work : AR0410c (R.C.C. foundation , plinth band and footings bases of columns mass concrete precast slabs etc) : Rigid and smooth centring and shuttering for R.C.C. works including false works and dismantling them after casting including cost of materials complete in ground floor R.C.C. foundation, plinth band and footings bases of columns mass concrete precast slabs, etc			
	41.088	Square Meter	216.39264180804	8891.1408666087

Total Amount:	292391.38042483
----------------------	-----------------

Provision for Contingency (+) @	3000
---------------------------------	------

Display Citizen Board (+) @	4500
Any Other Lumpsum (+) @	108.61
Provision for survey investigation and quality control (+) @	

Total Amount:	299999.99042483
----------------------	-----------------

Grand Net Total Amount	299999.99042483
-------------------------------	-----------------

Sarbeswar Sahu
JE
Nuagada Block

Pradiumna kumar dash
AEE
Nuagada Block

Loknath Sabar
BDO
Nuagada Block