

**Estimate Abstract**

**OD/353/3361/117525/414280/00070965 : Construction Of C C Road From PMGSY road to Chanapada in  
Convergence with MGNREGA  
Block : Nuagada, Gram Panchayat : Khajuripada  
Created By:Prasant kumar mallick**

Sl No	Quantity	Unit	Rate in (Rs.)	Amount (Rs.)
1	<b>Earth Work : AR0103a (Earth work in stoney earth and gravels mixed with stone and boulder not exceeding 0.014cum in volume within 50m. Initial lead and 1.5m initial lift) :</b> Earth work in stoney earth and gravels mixed with stone and boulder not exceeding 0.014cum in volume within 50m. Initial lead and 1.5m initial lift including rough dressing and breaking clods to maximum 5cm to 7cm and laying in layer not exceeding 0.3m in depth and as per specification approved by the department			
	30.57444	Cubic Meter	312.915372	9567.2122662917
2	<b>Earth Work : AR0115 (Filling foundation and plinth with sand well watered and rammed) :</b> Filling foundation and plinth with sand well watered and rammed including cost, conveyance, royalty, taxes of all materials, labours and T & P required for the work etc. complete and as per direction of Engineer-in charge.			
	16.0056	Cubic Meter	1151.403232	18428.899570099
3	<b>Concrete : AR0303a (Cement concrete (1:3:6) with 4 cm. hard granite(Hand Broken) metal) :</b> Cement concrete (1:3:6) with 4 cm. hard granite(Hand Broken) metal including laying in layers not exceeding 300 mm in depth, ramming, compacting to proper thickness, watering and curing for proper period with cost conveyance, royalty, taxes of all materials, labour and T&P required for the work etc. complete and as per direction of Engineer-in charge.			
	23.10984	Cubic Meter	5431.20063572	125514.17769939
4	<b>Concrete : AR0307 (Cement concrete (1:2:4)with 12mm size hard broken granite chips per 1cum) :</b> Cement concrete work with (1:2:4) using 12mm size hard granite(crusher broken) chips including hoisting and laying in position compacting to specified design section and curing for proper period with cost conveyance, royalty, taxes of all materials, labour and T&P required for the work etc. complete as per specifaicaion and direction of Engineer-in charge.			
	17.082	Cubic Meter	7559.60130164	129133.10943461
5	<b>R.C.C. Work : AR0410c (R.C.C. foundation , plinth band and footings bases of columns mass concrete precast slabs etc) :</b> Rigid and smooth centring and shuttering for R.C.C. works including false works and dismantling them after casting including cost of materials complete in ground floor R.C.C. foundation, plinth band and footings bases of columns mass concrete precast slabs, etc			
	44.928	Square Meter	216.39264180804	9722.0886111516

<b>Total Amount:</b>	292365.48758154
----------------------	-----------------

Provision for Contingency (+) @	3000
---------------------------------	------

Display Citizen Board (+) @	4500
Any Other Lumpsum (+) @	134.51
Provision for survey investigation and quality control (+) @	

<b>Total Amount:</b>	299999.99758154
----------------------	-----------------

<b>Grand Net Total Amount</b>	299999.99758154
-------------------------------	-----------------

**Prasant kumar mallick**  
**JE**  
**Nuagada Block**

**Pradiumna kumar dash**  
**AEE**  
**Nuagada Block**

**Loknath Sabar**  
**BDO**  
**Nuagada Block**