

Estimate Abstract

**OD/344/3278/115621/404223/00064260 : Const of cc road from Duryodhan house to ranjan sahu house
Block : Banarpal, Gram Panchayat : Kumanda
Created By: Biranchi Narayana Sahoo**

Sl No	Quantity	Unit	Rate in (Rs.)	Amount (Rs.)
1	Earth Work : AR0102aa (Earth work in hard soil or gravelly soil foundation & plinth within 50m. Initial lead and 1.5m initial lift) : Earth work in hard soil or gravelly soil foundation & plinth within 50m. Initial lead and 1.5m initial lift including rough dressing and breaking clods to maximum 5cm to 7cm and laying in layers not exceeding 0.3m in depth and as per the direction of the Engineer-in-charge			
	2.7	Cubic Meter	240.77592	650.094984
2	Earth Work : AR0115 (Filling foundation and plinth with sand well watered and rammed) : Filling foundation and plinth with sand well watered and rammed including cost, conveyance, royalty, taxes of all materials, labours and T & P required for the work etc. complete and as per direction of Engineer-in charge.			
	13.05	Cubic Meter	632.667232	8256.3073776
3	Concrete : AR0303 (Cement concrete (1:3:6) with 4 cm. Crusher Broken hard granite metal) : Cement concrete (1:3:6) with 4 cm. hard granite(Crusher Broken) metal including laying in layers not exceeding 300 mm in depth, ramming, compacting to proper thickness, watering and curing for proper period with cost conveyance, royalty, taxes of all materials, labour and T&P required for the work etc. complete and as per direction of Engineer-in charge.			
	11.25	Cubic Meter	5732.37260238	64489.191776775
4	Concrete : AR0307 (Cement concrete (1:2:4)with 12mm size hard broken granite chips per 1cum) : Cement concrete work with (1:2:4) using 12mm size hard granite(crusher broken) chips including hoisting and laying in position compacting to specified design section and curing for proper period with cost conveyance, royalty, taxes of all materials, labour and T&P required for the work etc. complete as per specification and direction of Engineer-in charge.			
	15.975	Cubic Meter	7168.70659906	114520.08791998
5	R.C.C. Work : AR0410c (R.C.C. foundation , plinth band and footings bases of columns mass concrete precast slabs etc) : Rigid and smooth centring and shuttering for R.C.C. works including false works and dismantling them after casting including cost of materials complete in ground floor R.C.C. foundation, plinth band and footings bases of columns mass concrete precast slabs, etc			
	36	Square Meter	216.23489289764	7784.456144315

Total Amount:	195700.13820267
----------------------	-----------------

Provision for Contingency (+) @	1010
Display Citizen Board (+) @	3900

Any Other Lumpsum (+) @	1308.86
Provision for survey investigation and quality control (+) @	
Total Amount:	201918.99820267
Grand Net Total Amount	201918.99820267

Biranchi Narayana Sahoo
JE
Banarpal Block

Biswamohan Patnaik
AEE
Banarpal Block

LOCHAN DAS
BDO
Banarpal Block