

Estimate Abstract

**OD/359/3424/118890/417393/00065537 : Const. of Paver road at Didrabadi, Kakamaha Sahi
Block : Daringibadi, Gram Panchayat : Badabanga
Created By:S MANOJ KUMAR PRUSTY**

Sl No	Quantity	Unit	Rate in (Rs.)	Amount (Rs.)
1	Earth Work : AR0102aa (Earth work in hard soil or gravelly soil foundation & plinth within 50m. Initial lead and 1.5m initial lift) : Earth work in hard soil or gravelly soil foundation & plinth within 50m. Initial lead and 1.5m initial lift including rough dressing and breaking clods to maximum 5cm to 7cm and laying in layers not exceeding 0.3m in depth and as per the direction of the Engineer-in-charge			
	21.6568	Cubic Meter	240.77592	5214.435944256
2	Earth Work : AR0115 (Filling foundation and plinth with sand well watered and rammed) : Filling foundation and plinth with sand well watered and rammed including cost, conveyance, royalty, taxes of all materials, labours and T & P required for the work etc. complete and as per direction of Engineer-in charge.			
	24.127	Cubic Meter	1039.555832	25081.363558664
3	miscellaneous : ARM287 (Supplying and fixing of 80mm thick cement concrete interlocking paver block of M-40 grade of approved make, design, colour and size made by Block making machine with proper compaction laid in required pattern etc. complete in all respect conforming to IRC) : Supplying and fixing of 80mm thick cement concrete interlocking paver block of M-40 grade of approved make, design, colour and size made by Block making machine with proper compaction laid in required pattern etc. complete in all respect conforming to IRC SP-63:2018. (New miscellaneous items) and as directed by Engineer-in-Charge.			
	146.74	Square Meter	637.5648	93556.258752
4	Concrete : AR0307 (Cement concrete (1:2:4)with 12mm size hard broken granite chips per 1cum) : Cement concrete work with (1:2:4) using 12mm size hard granite(crusher broken) chips including hoisting and laying in position compacting to specified design section and curing for proper period with cost conveyance, royalty, taxes of all materials, labour and T&P required for the work etc. complete as per specification and direction of Engineer-in charge.			
	7.6176	Cubic Meter	7530.83333428	57366.876007211
5	R.C.C. Work : AR0410c (R.C.C. foundation , plinth band and footings bases of columns mass concrete precast slabs etc) : Rigid and smooth centring and shuttering for R.C.C. works including false works and dismantling them after casting including cost of materials complete in ground floor R.C.C. foundation, plinth band and footings bases of columns mass concrete precast slabs, etc			
	18.4	Square Meter	216.39264180804	3981.6246092679
Total Amount:				185200.5588714
Provision for Contingency (+) @				2020

Display Citizen Board (+) @	3000
Any Other Lumpsum (+) @	11817
Provision for survey investigation and quality control (+) @	

Total Amount:	202037.5588714
----------------------	----------------

Grand Net Total Amount	202037.5588714
-------------------------------	----------------

S MANOJ KUMAR PRUSTY
JE
Daringibadi Block

SANJAYA KUMAR RATH
AEE
Daringibadi Block

PRITI RANJAN RATH
BDO
Daringibadi Block