

Estimate Abstract

**OD/363/3479/119928/430002/00070351 : Const. of CC road at Tankubeda from Majhi sahi to Talasahi
Block : Semiliguda, Gram Panchayat : Upparkanti
Created By:SMT PREETIMAYEE PANIGRAHI**

Sl No	Quantity	Unit	Rate in (Rs.)	Amount (Rs.)
1	Earth Work : AR0102aa (Earth work in hard soil or gravelly soil foundation & plinth within 50m. Initial lead and 1.5m initial lift) : Earth work in hard soil or gravelly soil foundation & plinth within 50m. Initial lead and 1.5m initial lift including rough dressing and breaking clods to maximum 5cm to 7cm and laying in layers not exceeding 0.3m in depth and as per the direction of the Engineer-in-charge			
	6.195	Cubic Meter	240.77592	1491.6068244
2	Earth Work : AR0115 (Filling foundation and plinth with sand well watered and rammed) : Filling foundation and plinth with sand well watered and rammed including cost, conveyance, royalty, taxes of all materials, labours and T & P required for the work etc. complete and as per direction of Engineer-in charge.			
	4.8675	Cubic Meter	783.813732	3815.21334051
3	Concrete : AR0303 (Cement concrete (1:3:6) with 4 cm. Crusher Broken hard granite metal) : Cement concrete (1:3:6) with 4 cm. hard granite(Crusher Broken) metal including laying in layers not exceeding 300 mm in depth, ramming, compacting to proper thickness, watering and curing for proper period with cost conveyance, royalty, taxes of all materials, labour and T&P required for the work etc. complete and as per direction of Engineer-in charge.			
	11.9475	Cubic Meter	5897.3760418	70458.900259406
4	R.C.C. Work : AR0410c (R.C.C. foundation , plinth band and footings bases of columns mass concrete precast slabs etc) : Rigid and smooth centring and shuttering for R.C.C. works including false works and dismantling them after casting including cost of materials complete in ground floor R.C.C. foundation, plinth band and footings bases of columns mass concrete precast slabs, etc			
	10.325	Square Meter	217.02363744964	2240.7690566675
5	Concrete : AR0307 (Cement concrete (1:2:4)with 12mm size hard broken granite chips per 1cum) : Cement concrete work with (1:2:4) using 12mm size hard granite(crusher broken) chips including hoisting and laying in position compacting to specified design section and curing for proper period with cost conveyance, royalty, taxes of all materials, labour and T&P required for the work etc. complete as per specifaion and direction of Engineer-in charge.			
	7.965	Cubic Meter	7390.5878976	58866.032604384

Total Amount:	136872.52208537
----------------------	-----------------

Provision for Contingency (+) @	1440
Display Citizen Board (+) @	4035

Any Other Lumpsum (+) @	1440
Provision for survey investigation and quality control (+) @	

Total Amount:	143787.52208537
----------------------	-----------------

Grand Net Total Amount	143787.52208537
-------------------------------	-----------------

SMT PREETIMAYEE PANIGRAHI
JE
Semiliguda Block

ER TOPHAN KUMAR NAYAK
AEE
Semiliguda Block

JASHMIN KUMAR PRADHAN
BDO
Semiliguda Block